Project: Maintenance/Repainting and Restoration of Light House (MPF-MOC-35-2025)
Location: Baseport and Terminal Ports

ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
1.00	**Fence and Masonry Works**	1.00	LOT		
	Work Description				
	Supply of materials, labor and equipment for fence and masonry works				
	Materials				
	A. FENCE				
	6mm x 75x75mm x 6m. G.I. Square Tube	4.00	pcs		
	6mm x 50x50mm x 6m. G. I. Square Tube	8.00	pcs		
	No. 8 Steel Matting 50x50 Mesh 4' x 8'	12.00	pcs		
	3mm thk.x 25x25mm Angle Bar x 6m	25.00	pcs		
	50mm dia. G.I. Pipe Sch 40 x 6m.	2.00	pcs		
	38mm dia. G.I. Pipe Sch 40 x 6m.	3.00	pcs		
	4"dia.x0.04"x5/8" Cutting Disk	5.00	box		
	1/8 Welding Rod 6012	5.00	box		
	Razor Barbed Wire X 10M	2.00	roll		
	8mm dia. Plain Bar x6m.	3.00	pcs		
	B. MASONRY				
	Portland Cement (40 kls)	10.00	bag		
	Washed Sand	5.00	cu.m.		
	3/4 Crushed Gravel	2.00	cu.m.		
	Manpower				
	1 Foreman	7.00	day(s)		
	2 Skilled Labor	7.00	day(s)		
	2 Unskilled Labor	7.00	day(s)		
	Equipment				
	2 welding machine	7.00	day(s)		
	1 grinder	7.00	day(s)		
			ESTIMATED DIRECT COST		₱
			ESTIMATED INDIRECT COST		₱
			TOTAL COST OF WORK ITEM 1.00		₱
2.00	**Steel Structures, Painting and Electrical Works**	1.00	LOT		
	Work Description				
	Supply of materials, labor and equipment for steel structures, painting and electrical works for the repair and maintenance of lighthouse				
	Materials				
	a. PAINTING				
	Flat Latex White	6.00	gal		
	Elastomeric Water Proofing Acrylic Paint White	12.00	gal		
	Epoxy Primer White	6.00	gal		
	Epoxy Reducer	3.00	gal		

ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
	Quick Dry Enamel White	10.00	gal		
	Lacquer Thinner	3.00	gal		
	Paint Thinner	5.00	kgs		
	Paint Roller 7" with tray	8.00	set		
	Baby Roller Cotton	8.00	set		
	2" Paint Brush	8.00	pcs		
	rust converter	1.00	gal		
	b. STEEL STRUCTURES				
	8mm x 100 x 100mm Angle Bar Galvanized x 6m.	1.00	pcs		
	6mm x 75 x 75mm Angle Bar Galvanized x 6m.	2.00	pcs		
	1/8 dia. Welding Rod-6012	2.00	box		
	4" Cutting Disk	3.00	box		
	No. 16 Plain Sheet 4'x8'	1.00	pcs		
	c. ELECTRICAL				
	Navigational Light (Light House) - Solar	1.00	set		
	No. 12 Stranded Copper Wire THHN	4.00	roll		
	Electrical Tape	5.00	roll		
	Rubber Tape	5.00	roll		
	3/4" dia, PVC Pipe x 10'	55.00	pcs		
	Manpower				
	1 Foreman	7.00	day(s)		
	2 Skilled Labor	7.00	day(s)		
	2 Unskilled Labor	7.00	day(s)		
	Equipment				
	1 welding machine	3.00	day(s)		
	1 grinder	3.00	day(s)		
	4 Steel Scaffolds, 1 set	3.00	day(s)		
			ESTIMATED DIRECT COST		P
			ESTIMATED INDIRECT COST		P
			TOTAL COST OF WORK ITEM 2.00		P
3.00	**Fabrication Works of Steel Hand Rail**	1.00	LOT		
	Work Description				
	Supply of materials, labor and equipment for Fabrication Works of Steel Hand Rail				
	Materials				
	a. FABRICATION OF STAIR HAND RAIL				
	50mm dia G.I. Pipe Sch 40 x 6m.	2.00	pcs		
	38mm dia. G.I. Pipe Sch 40 x 6m.	3.00	pcs		
	1/8 Welding Rod	1.00	box		
	4" dia. Cutting Disk Tyrolit	1.00	box		
	Epoxy Primer White	1.00	gal		
	Enamel White	1.00	gal		

ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
	Portland Cement	1.00	bag		
	Wash Sand	3.00	sack		
	3/4 Crushed Gravel	3.00	sack		
	Paint Thinner	3.00	gal		
	Baby Roller Cotton with Handle	2.00	set		
	2" Paint Brush	2.00	pcs		
	No. 8 Steel Matting 50x50 Mesh 4' x 8'	2.00	pcs		
	1/8 dia. Welding Rod-6012	1.00	box		
	b. GATE				
	No. 8 Steel Matting 50x50 Mesh 4' x 8'	2.00	pcs		
	38mm dia. G.I. Pipe Sch 40 x 6m.	7.00	pcs		
	16mm dia. Barrel Hinges	4.00	pcs		
	3mmx25x25mm Angle Bar	9.00	pcs		
	Manpower				
1	Foreman	3.00	day(s)		
2	Skilled Labor	3.00	day(s)		
2	Unskilled Labor	3.00	day(s)		
	Equipment				
1	welding machine	3.00	day(s)		
1	grinder	2.00	day(s)		
			ESTIMATED DIRECT COST		P
			ESTIMATED INDIRECT COST		P
			TOTAL COST OF WORK ITEM 3.00		P

BID AMOUNT IN WORDS :

_____

_____

NAME OF BIDDER ::

_____

SIGNATURE:

_____