Project: **Maintenance of Gate, Signages and Security Fence, Port of Opol (MPF-MOC-62-2025)**

Location: Port of Opol

ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
1.0	**Structural Concrete, CHB laying and Plastering**	1.00	lot		
	Work Description				
	Supply of Materials, Labor and equipment for the Structural Concrete, CHB laying and Plastering				
	Materials				
	SECURITY FENCE				
	150mm CHB Ordinary	711.00	pcs		
	Portland Cement	83.00	bags		
	Sand	3.00	cu.m		
	10mm dia. Deformed Bar	178.00	kgs		
	GI Tie Wire # 16	3.00	kgs		
	PLASTERING				
	Cement	37.00	bags		
	Sand	3.00	cu.m		
	STRUCTURAL CONCRETE (COLUMN)				
	Portland Cement	25.00	bags		
	Sand	2.00	cu.m		
	3/4 Gravel	3.00	cu.m		
	1/2"Ordinary Plywood	2.00	pcs		
	Good Lumber	46.00	bd.ft		
	Assorted Common Nails	10.00	kgs		
	concrete epoxy a & b	1.00	set		
	Manpower				
1	Foreman	7.00	day(s)		
3	Skilled Labor	7.00	day(s)		
4	Unskilled Labor	7.00	day(s)		
	Equipment				
1	One-bagger Mixer	7.00	day(s)		
1	Jackhammer	7.00	day(s)		
			ESTIMATED DIRECT COST		₱
			ESTIMATED INDIRECT COST		₱
			TOTAL COST OF WORK ITEM I.		₱

ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
2.0	**Reinforcement Steel Bar**	1.00	lot		
	Work Description				
	Supply of Materials, Labor and equipment for the Reinforcement Steel Bar				
	Materials				
	12mm dia.x 6m Deformed steel bar	18.00	lhs		
	10mm dia.x 6m Deformed steel bar	30.00	lhs		
	GI Tie Wire # 16	15.00	kgs		
	Manpower				
1	Foreman	1.00	day(s)		
1	Skilled Labor	1.00	day(s)		
2	Unskilled Labor	1.00	day(s)		
	Equipment				
	Minor Tools				
			ESTIMATED DIRECT COST		₱
			ESTIMATED INDIRECT COST		₱
			TOTAL COST OF WORK ITEM II.		₱
3.0	**CHB laying and Plastering**	1.00	lot		
	Work Description				
	Supply of Materials, Labor and tools for the Installation of GI pipe , Cyclone and Barbed Wire				
	Materials				
	GA10 Cyclone wire 5ftx6mx3mm (3inch)	9.00	pcs		
	Barbed Wire G.I GA12 (130m/roll)	3.00	roll		
	2" dia. GI Pipe shed 40	9.00	pcs		
	10mm dia. Round bar	27.00	lhs		
	Welding rod.	12.00	kgs		
	75mm dia PVC Pipe	2.00	pcs		
	Manpower				
1	Foreman	2.00	day(s)		
2	Skilled Labor	2.00	day(s)		
2	Unskilled Labor	2.00	day(s)		
	Equipment				
	Minor Tools				
			ESTIMATED DIRECT COST		₱
			ESTIMATED INDIRECT COST		₱
			TOTAL COST OF WORK ITEM III.		₱

ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
4.0	**Painting Works Fence and Gate**	109.44 sq.m.	kgs		
	Work Description				
	Supply of Materials, Labor and tools for the Painting Works of Perimeter Fence				
	Materials				
	PAINTING WORKS				
	Concrete Neutralizer	3.00	gal.		
	Flat latex	5.00	gal.		
	Patching Compound	5.00	gal.		
	Latex Semi-gloss	9.00	gal.		
	Quick Dry Enamel	2.00	gal.		
	Paint thinner	1.00	gal.		
	consumables				
	Manpower				
1	Foreman	3.00	days		
6	Skilled Labor	3.00	days		
3	Unskilled Labor	3.00	days		
	Equipment				
	Minor Tools				
		ESTIMATED DIRECT COST			₱
		ESTIMATED INDIRECT COST			₱
		TOTAL COST OF WORK ITEM IV.			₱
5.0	**Signage Steel Structure**	39.14	sq.m		
	Work Description				
	Supply of Materials and Labor for the Signages of Steel Structure				
	Materials				
	Fabrication of Reflective Sticker Signages including				
	Supply of materials and installation				
	1.2m H x 10m W Aluminum Cladding	1.00	set.		
	1.2m Hx 2.4m W x 3mm thk Aluminum Sheet	1.00	set.		
	Steel Main Post and Beam				
	75mm GI Pipe sched 40	2.00	pc.		
	50mm GI Pipe sched 40	38.00	pc.		
	25mm GI pipe sched 40	11.00	pc.		
	welding rod	28.00	kg.		

Continued at the Next Page

ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
	Painting Works				
	Epoxy Primer Gray	2.00	gal.		
	Quick Dry Enamel	5.00	gal.		
	Paint Thinner	2.00	gal.		
	Paint Brush 2""	4.00	pc.		
	50W LED Flood light	4.00	pc.		
	Consumables				
	Manpower				
1	Foreman	7.00	days		
3	Skilled Labor	7.00	days		
3	Unskilled Labor	7.00	days		
	Equipment				
1	Welding Machine	7.00	days		
1	Boom Truck	7.00	days		
	Minor Tools				

ESTIMATED DIRECT COST	₱	
ESTIMATED INDIRECT COST	₱	
TOTAL COST OF WORK ITEM V.	₱	
TOTAL BID AMOUNT	₱	

AMOUNT IN WORDS :

NAME OF BIDDER:

SIGNATURE: