Project: **Maintenance of Perimeter Fence and Covered Walkway, Port of Balbagon (MPF-MOC-63-2025)**

Location: Port of Balbagon

ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
1.0	**Stainless Covered Walkway Framings**	1,271.40	kgs		
	Work Description				
	Supply of Materials, Labor and equipment for Stainless Covered Walkway Framings				
	Materials				
	Stainless Pipe 304 38mm dia.x2mmx6m	48.00	length		
	Stainless Pipe 304 25mmdia. x2mmx6m	7.00	length		
	Welding Rod	26.00	pcs		
	stainless flat bar 50mmx3mm	8.00	length		
	consumables				
	Manpower				
1	Foreman	4.00	day(s)		
2	Skilled Labor	4.00	day(s)		
2	Unskilled Labor	4.00	day(s)		
	Equipment				
1	Welding Machine	3.00	day(s)		
	Minor Tools				
		ESTIMATED DIRECT COST			P
		ESTIMATED INDIRECT COST			P
		TOTAL COST OF WORK ITEM I.			P
2.0	**Roofing and Painting Works**	1.00	lot		
	Work Description				
	Supply of Materials, Labor and equipment for the roofing and painting works				
	Materials				
	Dura curve roofing 0.4mmx1000mm	66.40	l.m		
	Tekscrew	576.00	pcs		
	Painting Works				
	Elastomeric Paint (two-coats)	267.00	gal		
	consumables				
	Manpower				
1	Foreman	16.00	day(s)		
1	Skilled Labor	16.00	day(s)		
2	Unskilled Labor	16.00	day(s)		

Continued at Next Page

ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
				ESTIMATED DIRECT COST	₱
				ESTIMATED INDIRECT COST	₱
				TOTAL COST OF WORK ITEM II.	₱
				TOTAL BID AMOUNT	₱

AMOUNT IN WORDS :

NAME OF BIDDER:

SIGNATURE: