Project: **Maintenance of Booths, Curbs, and Toilets at Gate 6, Port of Cagayan de Oro [MPF-MOC-55-2025]**

Location: Port of Misamis Oriental/Cagayan de Oro City

| ITEM | DESCRIPTION | QUANTITY | UNIT | UNIT COST | AMOUNT |
|---|---|---|---|---|---|
| 1.0 | **Removal/Disposal of Dilapidated Items (Doors, Door Frames, Sliding Windows, Fixtures, Ceilings, and Outlets)** | 1.00 | lot | | |
| | Work Description | | | | |
| | Supply of Labor & Equipment for the Removal/Disposal of Dilapidated Items (Doors, Door Frames, Sliding Windows, Ceilings, CR Fixtures, and Outlets) | | | | |
| | Materials | | | | |
| | NONE | | | | |
| | Manpower | | | | |
| | 1 Foreman | 9.00 | day(s) | | |
| | 2 Skilled Workers | 9.00 | day(s) | | |
| | 3 Unskilled Workers | 9.00 | day(s) | | |
| | Equipment | | | | |
| | 1 Mini Dump Truck | 5.00 | day(s) | | |
| | | ESTIMATED DIRECT COST | | | ₱ |
| | | ESTIMATED INDIRECT COST | | | ₱ |
| | | TOTAL COST OF WORK ITEM I. | | | ₱ |
| 2.0 | **Gate Booth Maintenance** | 1.00 | lot | | |
| | Work Description | | | | |
| | Supply Materials, Labor, and Equipment for the Repair and Installation of PVC Door Sets and Glass Door Sets | | | | |
| | Materials | | | | |
| | PVC Door, with Half Glass Panel, Louvers, and Door Jamb | 4.00 | set | | |
| | PVC Solid Door, with Louver, and Door Jamb | 3.00 | set | | |
| | Stainless Steel Rounded Door Knob | 7.00 | pcs | | |
| | Silicone Sealant Clear | 10.00 | pcs | | |
| | Aluminum Framed Glass Sliding Door | | | | |
| | with 6mm tempered glass | 1.00 | set | | |
| | Consumables | | | | |
| | Manpower | | | | |
| | 1 Foreman | 7.00 | day(s) | | |
| | 2 Skilled Workers | 7.00 | day(s) | | |
| | 2 Non-Skilled Workers | 7.00 | day(s) | | |
| | Equipment | | | | |
| | 1 Electric Drill | 7.00 | day(s) | | |
| | | ESTIMATED DIRECT COST | | | ₱ |
| | | ESTIMATED INDIRECT COST | | | ₱ |
| | | TOTAL COST OF WORK ITEM II. | | | ₱ |

| ITEM | DESCRIPTION | QUANTITY | UNIT | UNIT COST | AMOUNT |
|---|---|---|---|---|---|
| 3.0 | **Gate Booth Maintenance** | 1.00 | lot | | |
| | Work Description<br>Supply Materials, Labor, and Equipment for the Repair, Realignment, and Cleaning of Sliding Windows for Booths | | | | |
| | Materials | | | | |
| | Repair and Cleaning of Sliding Aluminum Windows | | | | |
| | includes realignment of rollers, lock mechanism | 1.00 | lot | | |
| | Microfiber Cloths | 15.00 | pc | | |
| | Non-abrasive scrubs | 5.00 | pc | | |
| | Glass Cleaner (Spray) | 3.00 | bottle | | |
| | Consumables | | | | |
| | Manpower | | | | |
| 1 | Foreman | 7.00 | day(s) | | |
| 2 | Skilled Workers | 7.00 | day(s) | | |
| 2 | Unskilled Workers | 7.00 | day(s) | | |
| | Equipment | | | | |
| 1 | Electric Drill | 4.00 | day(s) | | |
| 1 | Ladder | 7.00 | day(s) | | |
| | | ESTIMATED DIRECT COST | | | ₱ |
| | | ESTIMATED INDIRECT COST | | | ₱ |
| | | TOTAL COST OF WORK ITEM III. | | | ₱ |
| 4.0 | **Gate Booth Maintenance** | 1.00 | lot | | |
| | Work Description<br>Supply of Materials, Labor, and Equipment for the Removal of Hardened Bird Droppings on the Booths | | | | |
| | Materials | | | | |
| | Scraper | 5.00 | pc. | | |
| | Spray Bottle (with Cleaning Solution) | 3.00 | pc. | | |
| | Consumables | | | | |
| | Manpower | | | | |
| 1 | Foreman | 6.00 | days | | |
| 2 | Skilled Workers | 6.00 | days | | |
| 2 | Unskilled Workers | 6.00 | days | | |
| | Equipment | | | | |
| 1 | Ladder | 3.00 | days | | |
| | | ESTIMATED DIRECT COST | | | ₱ |
| | | ESTIMATED INDIRECT COST | | | ₱ |
| | | TOTAL COST OF WORK ITEM IV. | | | ₱ |

| ITEM | DESCRIPTION | QUANTITY | UNIT | UNIT COST | AMOUNT |
|---|---|---|---|---|---|
| 5.0 | **Gate Booth Maintenance** | 10.56 | sq.m | | |
| | Work Description<br>Supply of Materials, Labor, and Equipment for the Replacement and Repair of Ceilings and Outlets | | | | |
| | Materials | | | | |
| | 600mmx600mm aluminum perforated ceiling panel | 30.00 | pcs | | |
| | 2 Legs Suspension, Twin Clamps | 15.00 | pcs | | |
| | Triangle keel, L = 3.00m | 24.00 | pcs | | |
| | Perimeter Trims 23mm x 23mm x 3.0m | 5.00 | pcs | | |
| | Drywall Fastener | 33.00 | pcs | | |
| | Convenience Outlet, Grounded, 250V | 5.00 | pcs | | |
| | Faceplate | 2.00 | pcs | | |
| | Electrical Tape | 3.00 | roll | | |
| | Consumables | | | | |
| | Manpower | | | | |
| | 1 Foreman | 7.00 | days | | |
| | 2 Skilled Workers | 7.00 | days | | |
| | 2 Unskilled Workers | 7.00 | days | | |
| | Equipment | | | | |
| | NONE | | | | |
| | | | ESTIMATED DIRECT COST | | P |
| | | | ESTIMATED INDIRECT COST | | P |
| | | | TOTAL COST OF WORK ITEM V. | | P |
| 6.0 | **Toilet Maintenance** | 1.00 | lot | | |
| | Work Description<br>Supply of Materials, Labor, and Equipment for the Replacement of CR Fixtures and Ceilings | | | | |
| | Materials | | | | |
| | Standard Water Closet, Flush Type | 5.00 | set | | |
| | Urinals, Wall-hung, Manual Flush, including Flush Valve | 2.00 | set | | |
| | Handheld Bidet Spray, including valves | 5.00 | set | | |
| | Perforated powder-coated metal ceiling panel | 1.00 | lot | | |
| | Consumables | | | | |
| | Manpower | | | | |
| | 1 Foreman | 6.00 | days | | |
| | 2 Skilled Workers | 6.00 | days | | |
| | 3 Nonskilled Workers | 6.00 | days | | |

**Continued at the Next Page**

| ITEM | DESCRIPTION | QUANTITY | UNIT | UNIT COST | AMOUNT |
|---|---|---|---|---|---|
| | Equipment | | | | |
| | 1 Electric Drill | 6.00 | days | | |
| | | | ESTIMATED DIRECT COST | | ₱ |
| | | | ESTIMATED INDIRECT COST | | ₱ |
| | | | TOTAL COST OF WORK ITEM VI. | | ₱ |
| 7.0 | **Repainting of Curbs** | 299.09 | sq. m. | | |
| | Work Description | | | | |
| | Supply of Materials, Labor, and Equipment for the Repainting of Curbs along Booths and CRs | | | | |
| | Materials | | | | |
| | Concrete Epoxy Primer White | 8.00 | Gal | | |
| | Epoxy Reducer | 3.00 | Gal | | |
| | 7" Paint Roller with Tray | 5.00 | Pc | | |
| | Reflectorized Traffic Paint (Yellow) | 8.00 | Pc | | |
| | Reflectorized Traffic Paint (Black) | 8.00 | Gal | | |
| | Reflectorized Traffic Paint (White) | 8.00 | Gal | | |
| | Baby Roller Cotton with Tray | 6.00 | Pc | | |
| | 2" Paint Brush | 6.00 | Pc | | |
| | 3" Paint Brush | 6.00 | Pc | | |
| | 8" dia. Waste Pad | 8.00 | Pc | | |
| | Paint Thinner | 4.00 | Gal | | |
| | Manpower | | | | |
| | 1 Foreman | 9.00 | days | | |
| | 2 Skilled Worker | 9.00 | days | | |
| | 2 Non-Skilled Worker | 9.00 | days | | |
| | Equipment | | | | |
| | NONE | | | | |
| | | | ESTIMATED DIRECT COST | | ₱ |
| | | | ESTIMATED INDIRECT COST | | ₱ |
| | | | TOTAL COST OF WORK ITEM VII. | | ₱ |
| | | | TOTAL BID AMOUNT | | ₱ |

AMOUNT IN WORDS :

NAME OF BIDDER:

SIGNATURE: