Project: **Maintenance of Plumbing Fixtures at Block 12, Port of Cagayan de Oro [MPF-MOC-69-2025]**

Location: Port of Cagayan de Oro

ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
1.0	**Removal/Disposal of Existing Plumbing Fixtures and Clogs at Block 12**	1.00	lot		
	Work Description Supply of Labor and Materials for the Removal and Disposal of Existing/Faulty Plumbing Fixtures and Declogging at Block 12, Building 2				
	Materials				
	-nothing follows-				
	Manpower				
	1 Plumber	3.00	days		
	1 Skilled Labor	3.00	days		
	2 Unskilled Labor	3.00	days		
	Equipment				
	1 Electric Drill	2.00	day(s)		
	with Plumbing Tools				
			ESTIMATED DIRECT COST		₱
			ESTIMATED INDIRECT COST		₱
			TOTAL COST OF WORK ITEM I.		₱
2.0	**Installation of Plumbing Fixtures at Block 12 (Building 2)**	1.00	lot		
	Work Description Supply of Labor, Materials, and Equipment for the Installation of Plumbing Fixtures at Block 12 (Ground Floor)				
	Materials				
	Water Closet (WC) Set, Floor Mounted, with Flush Lever, Vitreous China, White, Tank Fittings included	6.00	set		
	WC Gasket Kit/Wax Ring	6.00	pc		
	WC Mounting Bolts	6.00	set		
	Angle Valve, 1/2" by 1/2"	3.00	pc		
	Angle Valve, 2 Way, 1/2" x 1/2" x 1/2"	6.00	pc		
	Nipple Connection, 1/2" x 1/2" x 2"	10.00	pc		
	Bidet Complete Set, with Holder, Stainless Steel	6.00	set		
	Flexible Hose, 1/2" x 1/2" x 12"	6.00	pc		
	Flexible Hose, 1/2" x 1/2" x 18"	5.00	pc		
	Urinal, Wall Hung, Vitreous China, White	3.00	pc		
	Urinal Flush Valve, Manual Flush	3.00	pc		
	Urinal Waste Outlet	3.00	pc		
	Lavatory Sink, Basin Type	5.00	pc		

CONTINUATION AT THE NEXT PAGE

ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
	Sink Drain Strainer	6.00	pc		
	Tubular P Trap, Stainless Steel	6.00	pc		
	Faucet, Wall Mounted, Stainless Steel	1.00	pc		
	Faucet Sink, Goose Neck, High Spout	6.00	pc		
	Two Way Wall Faucet, Dual Function, Stainless Steel	3.00	set		
	Shower Head, with Bar Handle, Flexible Hose, and Holder Set	3.00	set		
	Silicone Sealant, White	15.00	tube		
	Caulking Gun	4.00	pc		
	Teflon Tape Roll, 18mm x 0.075mm x 10m	12.00	roll		
	Consumables				
	Manpower				
1	Plumber	5.00	days		
1	Skilled Labor	5.00	days		
2	Unskilled Labor	5.00	days		
	Equipment				
1	Electric Drill	1.00	days		
	with Plumbing Tools				
				ESTIMATED DIRECT COST	₱
				ESTIMATED INDIRECT COST	₱
				TOTAL COST OF WORK ITEM II.	₱
3.0	**Installation of Plumbing Fixtures at Block 12 (Building 2)**	1.00	lot		
	Work Description				
	Supply of Labor, Materials, and Equipment for the Installation of Plumbing Fixtures at Block 12 (2nd Floor Admin & OPM)				
	Materials				
	Water Closet (WC) Set, Floor Mounted, with Flush Lever, Vitreous China, White, Tank Fittings included	5.00	set		
	WC Gasket Kit/Wax Ring	5.00	pc		
	WC Mounting Bolts	5.00	set		
	Angle Valve, 1/2" by 1/2"	1.00	pc		
	Angle Valve, 2 Way, 1/2" x 1/2" x 1/2"	5.00	pc		
	Nipple Connection, 1/2" x 1/2" x 2"	10.00	pc		
	Bidet Complete Set, with Holder, Stainless Steel	5.00	set		
	Flexible Hose, 1/2" x 1/2" x 12"	5.00	pc		
	Flexible Hose, 1/2" x 1/2" x 18"	3.00	pc		
	Urinal, Wall Hung, Vitreous China, White	1.00	pc		
	Urinal Flush Valve, Manual Flush	1.00	pc		

CONTINUATION AT THE NEXT PAGE

ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
	Urinal Waste Outlet	1.00	pc		
	Lavatory Sink, Basin Type	1.00	pc		
	Lavatory Sink, Floor Mounted Type	2.00	pc		
	Sink Drain Strainer	3.00	pc		
	Tubular P Trap, Stainless Steel	3.00	pc		
	Faucet Sink, Goose Neck, High Spout	2.00	pc		
	Faucet Sink, Single Handle, Stainless Steel	1.00	pc		
	Shower Set, with Faucet and Valve, Recessed, Stainless	3.00	set		
	Silicone Sealant, White	14.00	tube		
	Teflon Tape Roll, 18mm x 0.075mm x 10m	12.00	roll		
	Exhaust Fan Wall Mounted	1.00	pc		
	Consumables				
	Manpower				
1	Plumber	5.00	days		
1	Skilled Labor	5.00	days		
2	Unskilled Labor	5.00	days		
	Equipment				
1	Electric Drill	2.00	days		
	with Plumbing Tools				
				ESTIMATED DIRECT COST	₱
				ESTIMATED INDIRECT COST	₱
				TOTAL COST OF WORK ITEM III.	₱
4.0	**Installation of Plumbing Fixtures at Block 12 (Building 2)**	1.00	lot		
	Work Description				
	Supply of Labor, Materials, and Equipment for the Installation of Plumbing Fixtures at Block 12 (3rd Floor)				
	Materials				
	Water Closet (WC) Set, Floor Mounted, with Flush Lever, Vitreous China, White, Tank Fittings included	3.00	set		
	WC Gasket Kit/Wax Ring	3.00	pc		
	WC Mounting Bolts	3.00	set		
	Angle Valve, 1/2" by 1/2"	2.00	pc		
	Angle Valve, 2 Way, 1/2" x 1/2" x 1/2"	3.00	pc		
	Nipple Connection, 1/2" x 1/2" x 2"	8.00	pc		
	Bidet Complete Set, with Holder, Stainless Steel	3.00	set		
	Flexible Hose, 1/2" x 1/2" x 12"	3.00	pc		
	Flexible Hose, 1/2" x 1/2" x 18"	3.00	pc		

CONTINUATION AT THE NEXT PAGE

ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
	Urinal, Wall Hung, Vitreous China, White	2.00	pc		
	Urinal Flush Valve, Manual Flush	2.00	pc		
	Urinal Waste Outlet	2.00	pc		
	Lavatory Sink, Basin Type	3.00	pc		
	Sink Drain Strainer	3.00	pc		
	Tubular P Trap, Stainless Steel	3.00	pc		
	Faucet Sink, Goose Neck, High Spout	3.00	pc		
	Shower Set, with Faucet and Valve, Recessed, Stainless	1.00	set		
	Silicone Sealant, White	8.00	tube		
	Teflon Tape Roll, 18mm x 0.075mm x 10m	8.00	roll		
	Consumables				
	Manpower				
1	Plumber	3.00	days		
1	Skilled Labor	3.00	days		
2	Unskilled Labor	3.00	days		
	Equipment				
1	Electric Drill	1.00	days		
	with Plumbing Tools				
				ESTIMATED DIRECT COST	₱
				ESTIMATED INDIRECT COST	₱
				TOTAL COST OF WORK ITEM IV.	₱
5.0	**Installation of Plumbing Fixtures at Block 12 (Building 2 Grounds)**	1.00	lot		
	Work Description				
	Supply of Labor, Materials, and Equipment for the Installation of Plumbing Fixtures at Block 12 (Amenity Building 3)				
	Materials				
	Water Closet (WC) Set, Floor Mounted, with Flush Lever, Vitreous China, White, Tank Fittings included	2.00	set		
	Water Closet (WC) Set, Flush Bowl Open	1.00	set		
	WC Gasket Kit/Wax Ring	3.00	pc		
	WC Mounting Bolts	3.00	set		
	Angle Valve, 2 Way, 1/2" x 1/2" x 1/2"	2.00	pc		
	Nipple Connection, 1/2" x 1/2" x 2"	2.00	pc		
	Bidet Complete Set, with Holder, Stainless Steel	2.00	set		
	Flexible Hose, 1/2" x 1/2" x 12"	2.00	pc		
	Flexible Hose, 1/2" x 1/2" x 18"	2.00	pc		

CONTINUATION AT THE NEXT PAGE

ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
	Lavatory Sink, Basin Type	2.00	pc		
	Sink Drain Strainer	2.00	pc		
	Tubular P Trap, Stainless Steel	2.00	pc		
	Faucet Sink, Goose Neck, High Spout	2.00	pc		
	Faucet Sink, Wall Mounted	3.00	pc		
	Silicone Sealant, White	6.00	tube		
	Teflon Tape Roll, 18mm x 0.075mm x 10m	6.00	roll		
	Consumables				
	Manpower				
1	Plumber	2.00	days		
1	Skilled Labor	2.00	days		
2	Unskilled Labor	2.00	days		
	Equipment				
1	Electric Drill	2.00	days		
	with Plumbing Tools				

ESTIMATED DIRECT COST	₱	
ESTIMATED INDIRECT COST	₱	
TOTAL COST OF WORK ITEM V.	₱	
TOTAL BID AMOUNT	₱	

AMOUNT IN WORDS :

NAME OF BIDDER:

SIGNATURE: