Project: **Maintenance of Guardhouse for Baseport and Terminal Ports [MPF-MPC-66-2025]**

Location: Port of Cagayan de Oro

ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
1.0	**Maintenance of Dilapidated Guardhouse**	1.00	lot		
	Work Description Supply of materials, labor and Equipment for the replacement of guardhouse				
	Materials				
	1.) Post/Framing				
	3mm x 100 x 100 Galv. Square Tube	10.00	lhs		
	3mm x 50 x 100 Galv. Rectangular Tube	5.00	lhs		
	2mm x 50 x 75 C Purlins	30.00	lhs		
	2mm x 50 x 100 C Purlins	20.00	lhs		
	1/8" thk. 1" X 1" Angle Bar	25.00	lhs		
	1/8" thk. 1" Flat Bar	13.00	lhs		
	2.) Floor/Side Framing				
	3mm x 50 x 75 Galv. Rectangular tubeSquare bar	3.00	lhs		
	3mm x 50 x 50 Galv. Square tube	14.00	lhs		
	3mm x 50 x 100 Galv. Rectangular Tube	12.00	lhs		
	3.) Floor Finish				
	12"x12" Vinyl Tiles	135.00	pcs		
	Rugby	5.00	gal		
	4.) Roofing Works (11.85 sq. m)				
	0.40MM x 1.133m Corr. Blue Longspan roofing	93.00	l.m.		
	0.40MM thk x 0.4m x 2.4 m ridge roll	25.00	lhs		
	touch-up paiint	1.00	can		
	5.) Electrical Lines/Fixture				
	60W floodlight with solar panel	10.00	set		
	6.) Ceiling Works (54.45 sq. m.)				
	Galv. Metal Furring, 5m x 0.6mm thk	55.00	pcs		
	4.5mm thk. Hardiflex	25.00	pcs		
	7.) Others:				
	Sticker Logo Signages (Vinyl Print; Waterproof Sticker)	5.00	sets		
	stainless handle	5.00	pcs		
	12mm thk. X 250mm x 250mm steel plates	20.00	pcs		
	8mm dia. Barreled bolt	5.00	set		
	door hinges	10.00	pcs		
	3/4"thk. Marine plywood (local)	10.00	pcs		
	1/2"thk. Hardiflex	23.00	pcs		
	Epoxy primer	8.00	gals		
	Enamel White	16.00	gals		
	Flat Latex White	6.00	gals		
	Semi-Gloss White	12.00	gals		
	TO BE CONTINUED AT THE NEXT PAGE				

ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
	Body filler	10.00	gals		
	Lacquer Spot Putty	10.00	gals		
	Consumable (5% of Material cost)				
	Manpower				
	Steel Works				
1	Foreman	15.00	days		
2	Skilled Laborer	15.00	days		
2	Unskilled Laborer	15.00	days		
	Floor Finishes (incl. marine plywood inst. on flooring & counters, ceiling)				
1	Foreman	3.00	days		
2	Skilled Laborer	3.00	days		
2	Unskilled Laborer	3.00	days		
	Painting Works				
1	Foreman	21.00	days		
4	Skilled Laborer	21.00	days		
2	Unskilled Laborer	21.00	days		
	Roofing Works				
1	Foreman	4.00	days		
1	Skilled Laborer	4.00	days		
2	Unskilled Laborer	4.00	days		
	Electrical Works				
1	Skilled Laborer	1.50	days		
2	Unskilled Laborer	1.50	days		
2	Unskilled Laborer	4.00	days		
	Equipment				
1	Truck Mounted (2 Tons)	1.50	days		
2	Welding Machine	1.50	days		
	Minor Tools (10% of Labor Cost)				

ESTIMATED DIRECT COST	₱
ESTIMATED INDIRECT COST	₱
TOTAL COST OF WORK ITEM I.	₱
TOTAL BID AMOUNT	₱

AMOUNT IN WORDS :

NAME OF BIDDER:

SIGNATURE: