Project: **Maintenance of Cable Tray ,Port of Cagayan de Oro (MPF MOC-56-2025)**

Location: Port of Cagayan de Oro

ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
1.0	**Civil works for the fabrication and painting of brackets and supports for cable tray**	1.00	lot		
	Work Description To supply materials, labor, tools and equipment for the fabrication of brackets and supports of the cable tray and painting of cable tray				
	Materials				
	1 1/2" x 4 mm² Angle Bar	20.00	length		
	N-6011 Welding Rod	80.00	kgs		
	Expansion Bolt	100.00	pcs		
	Premium Acrylic Paint - Gray	10.00	gal		
	4" Paint Brush	2.00	pcs		
	3" Paint Brush	2.00	pcs		
	Paint Roller Tray	25.00	pcs		
	Pre-Fab Cable Tray 300mm W x 10mm D x 2400mm L	100.00	length		
	12" Cable Tie	20.00	pack		
	Manpower				
	1 Electrician	7.00	day(s)		
	3 Skilled Labor	7.00	day(s)		
	Equipment				
	1 Welding Machine	7.00	day(s)		
	1 Portable Grinder	7.00	day(s)		
			ESTIMATED DIRECT COST		₱
			ESTIMATED INDIRECT COST		₱
			TOTAL COST OF WORK ITEM I.		₱
2.0	**Identification and removal of dead wires/cable along pathway of wires**	1.00	lot		
	Work Description To supply labor, materials, tools and equipment for identification and removal of dead wires/cable along pathway of wires				
	Materials				
	2AC Non-Contact Voltage Detector, 200V AC to 1,000V AC	1.00	pc.		
	Digital Multimeter	1.00	pc.		
	Manpower				
	1 Electrician	5.00	day(s)		
	3 Unskilled Labor	5.00	day(s)		

Continued at the Next Page

ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
	Equipment				
	1 Portable Grinder	5.00	day(s)		
			ESTIMATED DIRECT COST		₱
			ESTIMATED INDIRECT COST		₱
			TOTAL COST OF WORK ITEM II.		₱
3.0	**Electrical works on the termination of power cable from main source to powerhouse facility**	1.00	lot		
	Work Description				
	To supply materials, labor, tools and equipment for replacement of fuse type				
	Materials				
	200 Amps 3 Pole Moulded Case Circuit Breaker	1.00	pc		
	175 Amps 3 Pole Moulded Case Circuit Breaker	1.00	pc		
	400A, 600V Manual Transfer Switch, Breaker Type	1.00	pc		
	350-500 MCM Solderless Connector	6.00	pcs		
	Electrical Tape	15.00	roll		
	Rubber Tape	10.00	roll		
	Weatherproof Panel Box Circuit Breaker Enclosure	3.00	pcs		
	Manpower				
	2 Electrician	5.00	day(s)		
	3 Skilled Labor	5.00	day(s)		
	Equipment				
	1 Heavy Duty Electric Drill	5.00	day(s)		
			ESTIMATED DIRECT COST		₱
			ESTIMATED INDIRECT COST		₱
			TOTAL COST OF WORK ITEM III.		₱
			TOTAL BID AMOUNT		₱

AMOUNT IN WORDS :

NAME OF BIDDER:

SIGNATURE: