Project: **Maintennance of PPA Logo Signages, Port of Benoni**

Location: Port of Benoni

ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
1.0	**Demolition,Excavation and Backfilling**	1.00	lot		
	Work Description				
	Supply of Materials, Labor and equipment for the Demolition,Excavation and Backfilling				
	Manpower				
1	Foreman	3.00	day(s)		
5	Unskilled Labor	3.00	day(s)		
	Equipment				
1	Jackhammer	1.00	day(s)		
1	Concrete Saw	1.00	day(s)		
		ESTIMATED DIRECT COST			₱
		ESTIMATED INDIRECT COST			₱
		TOTAL COST OF WORK ITEM I.			₱
2.0	**Structural Concrete (Footing and pedestal)**	1.00	lot		
	Work Description				
	Supply of Materials, Labor and equipment for the Structural Concrete (Footing and pedestal)				
	Materials				
	Portland Cement	16.00	bag		
	Sand	1.00	cu.m		
	3/4 Gravel	2.00	cu.m		
	1/2"Ordinary Plywood	1.00	pc.		
	Good Lumber	30.00	bd.ft		
	Assorted Common Nails	5.00	kg		
	16mmx6m deformed bar	8.00	lhs		
	10mmx6m deformed bar	6.00	lhs		
	GI Tie Wire # 16	3.00	kgs		
	Manpower				
1	Foreman	1.00	day(s)		
2	Skilled Labor	1.00	day(s)		
4	Unskilled Labor	1.00	day(s)		
	Equipment				
1	One-Bagger Mixer	1.00	day(s)		
	Minor Tools				
		ESTIMATED DIRECT COST			₱
		ESTIMATED INDIRECT COST			₱
		TOTAL COST OF WORK ITEM II.			₱

ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
3.0	**Billboard Frame and Signage**	1.00	lot		
	Work Description				
	Supply of Materials, Labor and equipment for the Billboard Frame and Signage				
	Materials				
	50mm dia. GI Pipe shed 40	9.00	pcs.		
	100mm dia. GI Pipe shed 40	8.00	pcs.		
	Angle bar 50mmx50mmx6mm	27.00	pcs.		
	50mmx50mmx2mm Square tube	7.00	pcs.		
	75mmx75mmx2mm Square tube	5.00	pcs.		
	welding rod	38.00	kgs.		
	12mm base plate	0.84	sq.m		
	25mm base plate	0.54	sq.m		
	25mmx600mm L-type anchor bolt	24.00	pcs.		
	Red oxide	4.00	gal		
	Tarpulin signage(33ftx15ft)	495.00	sq.ft		
	25mmx25mmx3mm angle bar	6.00	pcs.		
	consumables				
	Manpower				
1	Foreman	12.00	days		
2	Skilled Labor	12.00	days		
2	Unskilled Labor	12.00	days		
	Equipment				
1	Welding Machine	10.00	days		
1	Boom Truck	2.00	days		
	Minor Tools				

ESTIMATED DIRECT COST ₱ _____

ESTIMATED INDIRECT COST ₱ _____

TOTAL COST OF WORK ITEM III. ₱ _____

TOTAL BID AMOUNT ₱ _____

AMOUNT IN WORDS :

_____

_____

NAME OF BIDDER: _____ SIGNATURE: _____