



CANVASS FORM

Project Title and Code	Repainting of Building No. 1, Port of Cagayan de Oro (MPF-MOC-47-2026)
Approved Budget for the Contract (ABC), in words and figures	Nine Hundred Forty-Seven Thousand Two Hundred Twenty-One Pesos and 80/100 only (Php 947,221.80)
Procurement Mode	Small Value Procurement (Sec. 34, RA 12009)
Contract Duration	45 Calendar Days
Source of Funds	PPA Corporate Operating Budget (COB) CY 2026

Description	Unit	Qty.	Unit Cost	Amount	Statement of Compliance (Check if you comply)
<i>Note: Non-compliance with the minimum required specifications shall be grounds for disqualification</i>					
1.0 Exterior Repainting of Building 1	lot	1			
1.01 Supply of Labor, Materials, and Equipment for the Exterior Building (including interior for Ground Floor)					
A. Materials					
Acrytex Reducer	gals.	10.00			
Acrytex Primer	gals.	64.00			
Gloss Latex White (2 coats)	gals.	114.00			
Quick Dry Enamel	gals.	15.00			
Paint Thinner	gals.	10.00			
Odorless Paint Anti-bacterial paint	gals.	54.00			
Odorless Paint (Latex Primer)	gals.	27.00			
Body filler	gals.	4.00			
Quick Dry Enamel (Red) or approved equal	liters	3.00			
Quick Dry Enamel (Brown)) or approved equal	gals.	2.00			
Lacquer thinner	gals.	4.00			
consumables (5% of materials cost)					
B. Labor					
a) Repainting					
1 Foreman	days	42.00			
3 Skilled Worker	days	42.00			
2 Unskilled Worker	days	42.00			
b) Installation/Stripping of Scaffolds					
1 Foreman	days	31.00			
1 Skilled Worker	days	31.00			
3 Unskilled Worker	days	31.00			
C. Equipment					
a.) Repainting					
Minor Tools (10% of Labor Cost)					
b.) Scaffolds					
34 H-Frame 1.7 m x 1.2m w/ catwalk, set					
2 pcs H-frames					
4 pcs diagonal cross braces	days	15.00			
4 pcs horizontal brace					
8 pcs joint pins					
57 Shoring Jack, 3.8 m full extension	days	16.00			
73 Adjustable U-head Jack, 0.6m	days	16.00			
73 Adjustable Base Jack, 0.6m	days	16.00			
57 1-1/2" GI Pipe x 6.0 m	days	16.00			
15 1-1/2" GI Pipe x 3.0 m	days	16.00			
30 1-1/2" GI Pipe x 4.0 m	days	16.00			
196 1-1/2" GI Pipe x 1.0 m	days	16.00			
253 Tie Rod x 0.60m	days	16.00			
507 Round Wing Nut	days	16.00			
ESTIMATED DIRECT COST				P	
ESTIMATED INDIRECT COST				P	
TOTAL COST OF WORK ITEM 1.0				P	

Description		Unit	Qty.	Unit Cost	Amount	Statement of Compliance (Check if you comply)
<i>Note: Non-compliance with the minimum required specifications shall be grounds for disqualification</i>						
2.0	Project Billboard	lot	1			
2.01	Supply of Materials, Labor, and Equipment for the Project Billboard					
A. Materials						
	Tarpaulin, 4'x8'	pcs.	1.00			
	Good lumber	bd. Ft	47.60			
	Assorted Common Nails	kg	1.00			
B. Labor						
	1 Foreman	days	0.25			
	1 Skilled Labor (Carpenter)	days	0.25			
	1 Unskilled Labor	days	0.25			
C. Equipment						
ESTIMATED DIRECT COST					P	
ESTIMATED INDIRECT COST					P	
TOTAL COST OF WORK ITEM 2.0					P	
Project Title & Code		ABC		Total Bid Quotation		
Repainting of Building No. 1, Port of Cagayan de Oro (MPF-MOC-47-2026)		In Figures	Php 947,221.80			
		In Words	Nine Hundred Forty-Seven Thousand Two Hundred Twenty-One Pesos and 80/100 only			

After having carefully read and accepted your General Conditions, I/We quote you on the item(s) at prices noted above.

Printed Name / Signature
Position / Designation
Tel. No. / Cellphone No.
email address
Date: _____