Project: **Maintenance of Roofing at Baseport, Port of Cagayan de Oro (MPF-MOC-70-2025)**
Location: Building 2, Port of Cagayan de Oro

ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
1.0	**Maintenance of Roofing at Baseport**	1.00	lot		
	Work Description				
	Supply labor, materials and equipment for the maintenance of roofing at Building 2				
	Materials				
	a.) Replacement of spanish gutter including flashing				
	Pre-painted Spanish gutter x 8'	pcs	70.00		
	Pre-painted End flashing x 8' (Fascia cover)	pcs	70.00		
	blind rivets	pcs	400.00		
	Consumables				
	b.) Replacement of spandrel				
	1-1/2" x 1-1/2" x 3mm thk Angle Bar	pcs	4.00		
	welding rod	kgs	5.00		
	0.40mm thk pre-painted spandrel	l.m.	1,130.79		
	0.60mm thk. perforated pre-painted spandrel (4" x 8ft)	pcs	130.00		
	end moulding x 8ft	pcs	106.00		
	center moulding x 8ft	pcs	16.00		
	blind rivets	pcs	2,400.00		
	silicon sealant (dark color)	tube	4.00		
	Consumables				
	c.) Installaion of Exhaust fan				
	16" heavy duty exhaust fan	pcs	10.00		
	d.) cleaning/disinfection/deoderizing on inner ceiling				
	putty knife	pcs	4.00		
	hard brooms/brush	lot	1.00		
	plastic bags (environmental friendly)	packs	10.00		
	deodorizer (Odor Eliminator/eco friendly)	gals	4.00		
	disinfectant	gals	4.00		
	spray bottle (500ml)	pcs	8.00		
	Consumables				
	e.) Safety Personnel Protection (Full Body Harness) (to be turn-over upon project completion)	pcs	4.00		
	Manpower				
	a.) Replacement of spanish gutter including flashing				
1	Construction foreman	6.00	days		
1	Skilled Laborer	6.00	days		
1	Unskilled Laborer	6.00	days		
	b.) Replacement of spandrel				
1	Construction foreman	40.00	days		
2	Skilled Laborer	40.00	days		
2	Unskilled Laborer	40.00	days		
	c.) Installation of Exhaust fan				
1	Skilled Laborer	1.00	days		

1	Unskilled Laborer	1.00	days		
d.) cleaning/disinfection/deoderizing on inner ceiling					
1	Construction foreman	4.00	days		
1	Skilled Laborer	4.00	days		
3	Unskilled Laborer	4.00	days		
Equipment					
2	Scaffolds	40.00	days		
1	welding machine	1.00	days		
	Minor tools				

ESTIMATED DIRECT COST ₱

ESTIMATED INDIRECT COST ₱

TOTAL COST OF WORK ITEM I. ₱

TOTAL PROJECT COST ₱

AMOUNT IN WORDS :

NAME OF BIDDER:

SIGNATURE: