Project: **MAINTENANCE OF GLASS PARTITIONS AT PMO OFFICES, PORT OF CAGAYAN DE ORO (MPF-MOC-74-2025)**
Location: Port of Cagayan de Oro

ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
1.0	**12mm Thick Glass with Aluminum Frame and Complete Accessories**	1.00	lot		
	Work Description				
	Supply of Materials, Labor, and Equipment for the 12mm thick Glass with Aluminum Frame and complete accessories at PMO Offices				
	Materials				
	12mm thick Glass with Aluminum Frame and Complete Accessories				
	D1 - 4.6m x 2.7m Double Sliding Door with Fixed Glass	1.00	set/s		
	D2 - 1.52m x 2.7m Single Sliding Glass Door with Fixed Window	2.00	set/s		
	D3 - 3.6m x 2.7m Frameless Sliding Glass Door	1.00	set/s		
	D4 - 1m x 2.1m Single Swing Glass Door - Reused Glass Door	1.00	set/s		
	D5 - 1.2m x 2.1m Sliding Door	1.00	set/s		
	D6 - 0.8m x 2.1m Single Swing Glass Door with Fixed Glass - Reused Glass	1.00	set/s		
	D7-3.1m x 3.9m Double Sliding Door with Fixed Glass Reused Glass Door	1.00	set/s		
	Glass Tint	2.00	set/s		
	Consumables				
	Demolition and Restoration of Existing Concrete walls	1.00	lot		
	Removal of Existing Glass Partition and Door	1.00	lot		
	Manpower				
	1 Construction foreman	30.00	days		
	4 Skilled Labor	30.00	days		
	4 Unskilled Labor	30.00	days		
	Equipment				
	1 Cargo Truck	2.00	days		
	1 Cut-Off Machine	10.00	days		

ESTIMATED DIRECT COST ₱ _____

ESTIMATED INDIRECT COST ₱ _____

TOTAL COST OF WORK ITEM I. ₱ _____

TOTAL PROJECT COST ₱ _____

AMOUNT IN WORDS :

_____

_____

NAME OF BIDDER: _____

SIGNATURE: _____