

# ***SPECIFICATIONS – MOBILIZATION / DEMOBILIZATION***

## **SCOPE OF WORK**

This Section includes mobilization, demobilization, assembly and disassembly of equipment/plants including incidentals necessary to complete the work.

## **MOBILIZATION**

1. The Contractor shall mobilize and put into operation all equipment and plants required to undertake the Contract.
2. Mobilization shall include the transferring to the job-sites of all equipment, plants, supplies and materials, personnel, and all items necessary for the execution and completion of the work, and shall also include the setting up of all equipment, instruments and all other plants until rendered operable, subject to the confirmation of the Engineer.
3. Sufficient supply of spares for the equipment and plants shall be carried on-board the towing/carrying vessels. Equipment/plants encountering breakdowns must be repaired on site by the most expeditious method possible at no cost to PPA. In the event that the equipment/plants call for major repair works that cannot be undertaken at the site, the Contractor shall replace such equipment/plants with equal or better performance capacity at no additional mobilization costs to PPA and the Contractor shall not be entitled to any time extension.

## **DEMOBILIZATION**

Demobilization upon request of the Contractor and approved by the Engineer, shall include the following:

1. The dismantling, preparation and loading for removal and shipment of all Contractor's plant, equipment and personnel at each site after completion of the works.
2. Transportation of all the above plant, equipment and materials from each site to the Contractor's home station or somewhere else outside the sites.
3. Removal of all supplementary markers furnished and installed by the Contractor, provided that the Engineer has not taken the option to retain the markers.
4. The clean up of the Site and the removal of materials, debris, waste, etc., and making good damages or temporary alterations.

## **MEASUREMENT AND PAYMENT**

## ***SPECIFICATIONS – MOBILIZATION / DEMOBILIZATION***

Payment for this item includes the expenses incurred by the Contractor for moving-in of minimum major equipment and/or plant required for the project and moving out of the same after final acceptance of the work including cleaning-up. Fifty percent (50%) of the total amount shall be payable after mobilization activity while the remaining fifty percent (50%) payable after acceptance of the completed project. A list of equipment showing the detailed cost for its mobilization and demobilization works shall be included in the bid amount for this item.