BILL OF QUANTITIES

Project Name : Maintenance Repair of Sasa Port Container Yard Installed with Paving Blocks (Phase-1), Sasa Wharf, Davao City

Location : Sasa Port, Davao City

Item No.	Description	Unit	Quantity	Unit Cost	Amount
I	**Mobilization / Demobilization at Pesos:** _____ per lot	Lot	1.00		
II	**Removal and Disposal of Existing Paving Blocks & Shear Key at Pesos:** _____ per sq.m.	Sq.M.	4,772.40		
III	**Excavation/Backfill and Disposal at Pesos:** _____ per cu.m.	Cu.M.	3,579.30		
IV	**Supply and Compaction of Item 200 (Sub-Base Course) at Pesos:** _____ per cu.m.	Cu.M.	1,002.20		
V	**Supply and Compaction of Item 201 (Base Course) at Pesos:** _____per cu.m.	Cu.M.	1,002.20		

BILL OF QUANTITIES

Project Name : Maintenance Repair of Sasa Port Container Yard Installed with Paving Blocks (Phase-1), Sasa Wharf, Davao City

Location : Sasa Port, Davao City

Item No.	Description	Unit	Quantity	Unit Cost	Amount
VI	**Supply and Compaction of Gravel Base (CBR>80) at Pesos:** _____per cu.m.	Cu.M.	501.10		
VII	**Supply, Spread and Compaction of 10% Cement Treated Base Course at Pesos:** _____per cu.m.	Cu.M.	1,002.20		
VIII	**Supply and Place Sand Cushion at Pesos:** _____per cu.m.	Cu.M.	250.55		
IX	**Supply, Deliver and Install Interlocking Concrete Paving Blocks (6,000 psi) at Pesos:** _____**per sq.m.**	Sq.M.	4,400.00		
X	**Supply of Labor, Materials and Equipment for the Construction of Shear Key at Pesos:** _____**per ln.m.**	Ln.M.	186.20		

BILL OF QUANTITIES

Project Name : Maintenance Repair of Sasa Port Container Yard Installed with Paving Blocks (Phase-1), Sasa Wharf, Davao City

Location : Sasa Port, Davao City

Item No.	Description	Unit	Quantity	Unit Cost	Amount
XI	**Repair of Manhole (6-units) and Catch Basin (7-units) Covers at Pesos:** **_____per unit**	Units	13.00		
XII	**Supply of Labor, Materials and Equipment for the Fabrication/Installation of Project Billboard at Pesos:** **_____per lot**	Lot	1.00		
XIII	**Construction Safety and Health Program (as required under Department Order No. 13) at Pesos:** **_____per lot**	Lot	1.00		
Total Cost of Bid (inclusive of 12% VAT and all other taxes) >>>>>>>>>>>>>					**₱**
Amount in words					

Submitted By :

_____

Name and Signature of Authorized Representative