**BILL OF QUANTITIES**

**Project Name : Proposed Retrofitting of Mati Port, Mati City, Davao Oriental**

**Location : Mati Port, Mati City, Davao Oriental**

| Item No. | Description | Unit | Quantity | Unit Cost | Amount |
|---|---|---|---|---|---|
| **I** | **Mobilization / Demobilization at Pesos:**<br><br><br><br><br><br>_____ per lot | Lot | 1.00 | | |
| **II** | **Provision of Temporary Facilities, Bunkhouse, Warehouse, Field Office and Utilities at Pesos:**<br><br><br><br><br>_____ per lot | Lot | 1.00 | | |
| **III** | **Scrapping and Removal of Microorganisms from Pier Piles (Bent 1-17) West Portion of Mati Port at Pesos:**<br><br><br><br><br>_____ per sq.m. | Sq.M. | 537.60 | | |
| **IV** | **Supply and Application of Structural Epoxy on Cracked and Spalled Concrete (Scheme 1) at Pesos:**<br><br><br><br>_____ per gal/set | Gal/Set | 910.00 | | |

**BILL OF QUANTITIES**

**Project Name : Proposed Retrofitting of Mati Port, Mati City, Davao Oriental**

**Location : Mati Port, Mati City, Davao Oriental**

| Item No. | Description | Unit | Quantity | Unit Cost | Amount |
|---|---|---|---|---|---|
| **V** | **Supply and Application of Epoxy Mortar Including Placing of Cement Plaster to Replace Spalled/Damaged Concrete (Scheme 2) at Pesos:**<br><br>**_____per gal/set** | Gal/Set | 336.00 | | |
| **VI** | **Supply and Apply Underwater Epoxy Putty (Scheme 1 and 2) at Pesos:**<br><br>**_____ per gal/set** | Gal/Set | 250.00 | | |
| **VII** | **Supply and Application of Rust Converter on Corroded Steel Reinforcements at Pesos:**<br><br>**_____ per sq.m.** | Sq.M. | 103.86 | | |
| **VIII.** | **Supply and Application Epoxy Bonding Agent (Concrete Adhesive) (Scheme 2 and 3) at Pesos:**<br><br>**_____ per sq.m.** | Sq.M. | 22.58 | | |

**BILL OF QUANTITIES**

**Project Name : Proposed Retrofitting of Mati Port, Mati City, Davao Oriental**

**Location : Mati Port, Mati City, Davao Oriental**

| Item No. | Description | Unit | Quantity | Unit Cost | Amount |
|---|---|---|---|---|---|
| **IX.** | **Removal, Supply and Replacement of Steel Reinforcements for Underdeck and Underwater Damaged Portion of Exposed Corroded Rebars at Pesos:**<br><br>_____**per kg.** | Kgs. | 430.00 | | |
| **X.** | **Supply and Application of Two (2) Layers of Glass Fiber with Saturated Epoxy to Surfaces Above Water (unit cost of glass fiber is for one (1) layer only) at Pesos:**<br><br>_____**per sq.m.** | Sq.M. | 3,841.95 | | |
| **XI.** | **Supply and Application of Two (2) Layers of Glass Fiber with Saturated Epoxy to Surfaces Below Water (unit cost of glass fiber is for one (1) layer only) at Pesos:**<br><br>_____**per sq.m.** | Sq.M. | 2,426.43 | | |
| **XII.** | **Supply and Application of Miscellaneous Materials for Painting Works Including Accessories as Detailed in the Plan at Pesos:**<br><br>_____**per sq.m.** | Sq.M. | 2,742.22 | | |

**BILL OF QUANTITIES**

**Project Name : Proposed Retrofitting of Mati Port, Mati City, Davao Oriental**

**Location : Mati Port, Mati City, Davao Oriental**

| Item No. | Description | Unit | Quantity | Unit Cost | Amount |
|---|---|---|---|---|---|
| **XIII.** | **Supply of Labor, Materials and Equipment for the Fabrication/Installation of Project Billboard at Pesos:**<br><br>**_____per lot** | Lot | 1.00 | | |
| **XIV.** | **Construction Safety and Health Program (as required under Department Order No. 13) at Pesos:**<br><br>**_____per lot** | Lot | 1.00 | | |
| **Total Cost of Bid (inclusive of 12% VAT and all other taxes) >>>>>>>>>>>>>>** | | | | | **₱** |
| | | | | | |
| **Amount in words** | | | | | |

Submitted By :

_____

**Name and Signature of Authorized Representative**