BILL OF QUANTITIES

Project Name : Repair/Replacement of Light Tower HPS with LED Lamps at Sasa Port, Davao City

Location : Sasa Port, Davao City

Item No.	Description	Unit	Quantity	Unit Cost	Amount
I	**Mobilization / Demobilization at Pesos:** _____ per lot	Lot	1.00		
II	**Provide Safety & Health Program for the Project (as required under Department Order No. 13) at Pesos:** _____ per lot	Lot	1.00		
III	**Removal of Existing HPS Lamps and Disposal of Damaged Materials at Pesos:** _____ per unit	Units	96.00		
IV	**Supply and Deliver 400w LED Flood Lamps for 30m High Port Light Towers at Pesos:** _____ per unit	Units	96.00		
V	**Install 400w LED Flood Lamps for 30m High Port Light Towers at Pesos:**				

BILL OF QUANTITIES

Project Name : Repair/Replacement of Light Tower HPS with LED Lamps at Sasa Port, Davao City

Location : Sasa Port, Davao City

Item No.	Description	Unit	Quantity	Unit Cost	Amount
	_____ per unit	Units	96.00		
VI	**Retouching of Paints for Steel and PVC Electrical Pipes at Pesos:** _____ per lot	Lot	1.00		
Total Cost of Bid (inclusive of 12% VAT and all other taxes) >>>>>>>>>>>>>>					**₱**
Amount in words					

Submitted By :

_____

Name and Signature of Authorized Representative