BILL OF QUANTITIES

Project Name : Upgrading of Electrical Power Connection into Three Phase Power Supply

Location : Port of Babak, Island Garden City of Samal, Davao Del Norte

Item No.	Description	Unit	Quantity	Unit Cost	Amount
1.0	**Mobilization / Demobilization at Pesos:** _____ per lot	Lot	1.00		
2.0	**Excavation Works for Transformer Pad - Lay-out, Excavation Works for Footing and Tie Beam, Disposal of Excavated soil at Pesos:** _____ per cu.m.	Cu.M.	7.00		
3.0	**Rebar Works for Footing, Column, Tie Beam, and Slab for Transformer Pad at Pesos:** _____ per kg.	Kg.	2,143.00		
4.0	**Masonry Works for Filing of 4" CHB Wall & Plastering of CHB Wall and Concrete Structure for Transformer Pad at Pesos:** _____ per sq.m.	Sq.M.	12.00		
5.0	**Backfilling Up to Desired Elevation and Compaction of Filling Materials at Pesos:** _____per cu.m.	Cu.M.	4.00		

BILL OF QUANTITIES

Project Name : Upgrading of Electrical Power Connection into Three Phase Power Supply

Location : Port of Babak, Island Garden City of Samal, Davao Del Norte

Item No.	Description	Unit	Quantity	Unit Cost	Amount
6.0	**Concrete Works - Preparation of Forms, Concreting of Footing, Column, Beam, Slab for Transformer Pad and Installation of Downspout at Pesos:** _____per cu.m.	Cu.M.	16.00		
7.0	**Application of Waterproofing at Roof Deck (3-coats) at Pesos:** _____per sq.m.	Sq.M.	25.00		
8.0	**Painting Works - Application of Concrete Neutralizer for all Concrete Surfaces to be Painted Before Painting Start, Application of Rust Converter to All Steel Surface to be Painted, Painting of CHB wall, Exposed Beams and Columns at Pesos:** _____per sq.m.	Sq.M.	34.80		
9.0	**Installation of Disconnecting Equipments and Accessories (Main, Manual Transfer Switch (MTS) and Sub-Main Panel Boards) and Tapping of 3-Phase Source for POB Power Supply at Pesos:** _____per lot	Lot	1.00		

BILL OF QUANTITIES

Project Name : Upgrading of Electrical Power Connection into Three Phase Power Supply

Location : Port of Babak, Island Garden City of Samal, Davao Del Norte

Item No.	Description	Unit	Quantity	Unit Cost	Amount
10.0	**Provision of 3 Phase Pole Lines and Accessories at Pesos:**	Lot	1.00		
	_____per lot				
11.0	**Supply and Installation of 3-50Kva Oil Type PCB Free Transformer, Transformer Banking , Secondary Metering, Energizing, Commissioning and Testing at Pesos:**	Lot	1.00		
	_____per lot				
12.0	**Supply of Labor, Materials and Equipment for the Fabrication/ Installation of Project Billboard at Pesos:**	Lot	1.00		
	_____per lot				
13.0	**Construction Safety & Health Program (as required under DOLE D.O. No. 13 and PPA EC No. 01-2020) at Pesos:**	Lot	1.00		
	_____per lot				
Total Cost of Bid (inclusive of 12% VAT and all other taxes) >>>>>>>>>>>>>>					**₱**
Amount in words					

Submitted By :

_____

Name and Signature of Authorized Representative