BILL OF QUANTITIES

Project Name : Repair of Scattered Damaged Portland Cement Concrete Pavement (PCCP) at Sasa Port, Davao City

Location : Sasa Port, Davao City

Item No.	Description	Unit	Quantity	Unit Cost	Amount
I	**Mobilization / Demobilization at Pesos:** _____ per lot	Lot	1.00		
II	**Demolition and Disposal of Existing Pavement (thickness=0.30m) at Pesos:** _____ per sq.m.	Sq.M.	3,217.88		
III	**Excavation/Backfill and Disposal at Pesos:** _____ per cu.m.	Cu.M.	4,955.53		
IV	**Supply and Compaction of Item 200 for Sub-Base at Pesos:** _____per cu.m.	Cu.M.	772.30		

BILL OF QUANTITIES

Project Name : Repair of Scattered Damaged Portland Cement Concrete Pavement (PCCP) at Sasa Port, Davao City

Location : Sasa Port, Davao City

Item No.	Description	Unit	Quantity	Unit Cost	Amount
V	**Supply and Compaction of Item 201 for Base at Pesos:** **_____per cu.m.**	Cu.M.	772.30		
VI	**Supply, Deliver and Compact Selected Fill at Pesos:** **_____per cu.m.**	Cu.M.	3,217.88		
VII	**Supply, Fabricate and Install Reinforcing Bar for PCCP at Pesos:** **_____ per kg.**	Kgs.	30,885.22		
VIII.	**Reconcreting of Portland Cement Concrete Pavement (0.30m) at Pesos:** **_____ per sq.m.**	Sq.M.	3,217.88		

BILL OF QUANTITIES

Project Name : Repair of Scattered Damaged Portland Cement Concrete Pavement (PCCP) at Sasa Port, Davao City

Location : Sasa Port, Davao City

Item No.	Description	Unit	Quantity	Unit Cost	Amount
IX.	**Supply, Fabricate and Install Billboard at Pesos:** **_____per lot**	Lot	1.00		
X.	**Rehabilitate, Fabricate and Install Drainage Manhole Cover at Pesos:** **_____per unit**	Units	1.00		
XI.	**Construction Safety and Health Program (as required under Department Order No. 13) at Pesos:** **_____per lot**	Lot	1.00		
Total Cost of Bid (inclusive of 12% VAT and all other taxes) >>>>>>>>>>>>>					**₱**
Amount in words					

Submitted By :

_____

Name and Signature of Authorized Representative