BILL OF QUANTITIES

Project Name : Repair of Damaged Back-up Area and Provision of Drainage System

Location : Malalag Port, Malalag, Davao del Sur

Item No.	Description	Unit	Quantity	Unit Cost	Amount
1.0	**Mobilization / Demobilization at Pesos:** _____ per lot (**Amount in words)**	Lot	1.00		
2.0	**Demolition of Existing PCCP 21.55m x 34.75m (thickness = 0.25m) and Concrete Curb 49.4m x 0.25m at Pesos:** _____ per sq.m. (**Amount in words)**	Sq.M.	762.00		
3.0	**Excavation and Disposal unsuitable materials (for storm drainage) at Pesos:** _____ per cu.m. (**Amount in words)**	Cu.M.	106.00		
4.0	**Supply, Spread, and Compact of Aggregate Sub Base Coarse at Pesos:** _____ per cu.m. (**Amount in words)**	Cu.M.	180.00		
5.0	**Supply, Spread, and Compact of Aggregate Base Coarse at Pesos:** _____per cu.m. (**Amount in words)**	Cu.M.	180.00		

6.0	**Fabrication and Installation of Reinforcing Steel Bars for Concrete Pavement, Storm Drainage, and RC Curb at Pesos:**	Kgs.	17,078.00		
	_____per kg. (**Amount in words)**				
7.a	**Concrete Works for Pavement at Pesos:**	Cu.M.	184.80		
	_____per cu.m. (**Amount in words)**				
7.b	**Concrete Works for fence & RC curb at Pesos:**	Cu.M.	4.08		
	_____per cu.m. (**Amount in words)**				
7.c	**Concrete Works for drainage at Pesos:**	Cu.M.	59.12		
	_____per cu.m. (**Amount in words)**				
8.0	**Fabrication and installation of Hot Dipped steel gratings and catch basin covers for storm drainage at Pesos:**	Ln.M.	87.73		
	_____per ln.m. (**Amount in words)**				

9.0	**Painting Works at Pesos:** _____per sq.m. (**Amount in words)**	Sq.M.	313.12		
10.0	**Supply of labor, materials and equipment for the Fabrication/Installation of Project Billboard at Pesos:** _____per lot (**Amount in words)**	Lot	1.00		
11.0	**Construction Safety & Health Program (as required under DOLE D.O. No. 13 and PPA EC No. 01-2020) at Pesos:** _____per lot (**Amount in words)**	Lot	1.00		
Total Cost of Bid (inclusive of 12% VAT and all other taxes) >>>>>>>>>>>>>					**₱**
Amount in words					

Submitted By :

_____

Name and Signature of Authorized Representative