BILL OF QUANTITIES

Project Name : **Repair of Back-up Area at Berth No. 10 (Phase-3)**

Location : **Sasa Port, Davao City**

Item No.	Description	Unit	Quantity	Unit Cost	Amount
I	**Mobilization / Demobilization at Pesos:** **_____ per lot**	Lot	1.00		
II	**Removal and Disposal of Existing Paving Blocks at Pesos:** **_____ per sq.m.**	Sq.m.	3,595.97		
III	**Excavation/Backfill and Disposal at Pesos:** **_____ per cu.m.**	Cu.m..	5,244.36		
IV	**Supply, Deliver and Compaction of Selected Fill at Pesos:** **_____ per cu.m.**	Cu.m.	2,494.76		
V	**Supply, Deliver and Compaction of Item 200 for Sub-base Course at Pesos:** **_____ per cu.m.**	Cu.m.	755.15		

BILL OF QUANTITIES

Project Name : **Repair of Back-up Area at Berth No. 10 (Phase-3)**

Location : **Sasa Port, Davao City**

Item No.	Description	Unit	Quantity	Unit Cost	Amount
VI	**Supply, Deliver and Compaction of Item 201 for Base Course at Pesos:** **_____ per cu.m.**	Cu.m..	755.15		
VII	**Supply, Deliver and Compaction of Gravel Base (CBR>80) at Pesos:** **_____ per cu.m.**	Cu.m.	377.58		
VIII	**Supply, Deliver, Spread and Compaction of 10% Cement Treated Base Course at Pesos:** **_____ per cu.m.**	Cu.m.	755.15		
IX	**Supply, Deliver and Place Leveling Sand Cushion at Pesos:** **_____ per cu.m.**	Cu.m.	188.79		
X	**Supply, Deliver and Install Interlocking Concrete Paving Blocks (6000psi) at Pesos:**	Sq.m.	3,409.77		

BILL OF QUANTITIES

Project Name : **Repair of Back-up Area at Berth No. 10 (Phase-3)**

Location : **Sasa Port, Davao City**

Item No.	Description	Unit	Quantity	Unit Cost	Amount
	_____ per sq.m.				
XI	**Supply of Labor, Materials and Equipment for the Construction of Shear Key at Pesos:** **_____ per ln.m.**	Ln.M.	372.40		
XII	**Supply of Labor, Materials and Equipment for the Fabrication and Installation Manhole and Culverts at Pesos:** **_____ per ln.m.**	Ln.M.	40.00		
XIII	**Supply, Fabricate and Install Project Billboard at Pesos:** **_____ per lot.**	Lot	1.00		
XIV	**Construction Safety and Health Program (as required under Department Order No. 13) at Pesos:** **_____ per lot**	Lot	1.00		
Total Cost of Bid (inclusive of 12% VAT and all other taxes) >>>>>>>>>>>>>					**P**

BILL OF QUANTITIES

Project Name : **Repair of Back-up Area at Berth No. 10 (Phase-3)**

Location : **Sasa Port, Davao City**

Item No.	Description	Unit	Quantity	Unit Cost	Amount
Amount in words					

Submitted By :

_____

Name and Signature of Authorized Representative