

## BILL OF QUANTITIES

ZAM-PGEPCS-08-2019/ EP 06-2019

Busay Port Expansion Project, Port of Busay, Brgy Busay, Sacol Island, Zamboanga City

| Item No.          | Description   | Unit | Quantity  | Unit Cost | Amount |
|-------------------|---|------|-----------|-----------|--------|
| <b>Bill No. 1</b> | <b>GENERAL EXPENSES</b>   |      |           |           |        |
| 1.01              | Mobilization, Demobilization and Cleaning<br><i>at Pesos: _____ per Lot</i>   | lot  | 1.00      |           |        |
| 1.02              | Rental of Temporary Site Office and Residence for the Engineer and Staff<br><i>at Pesos: _____ per mo.</i>              | mo.  | 8.00      |           |        |
| 1.03              | Maintain temporary site office and residence for the Engineer and staff<br><i>at Pesos: _____ per cu.m</i>              | mo.  | 8.00      |           |        |
| 1.04              | Provide Construction Safety and Health Program in the execution of the Project<br><i>at Pesos: _____ per cu.m</i>       | mo.  | 8.00      |           |        |
| <b>Bill No. 2</b> | <b>UPGRADING AND EXTENSION OF EXISTING ROCK CAUSEWAY</b>  |      |           |           |        |
| 2.01              | Supply and place 5-20 kg rocks<br><i>at Pesos: _____ per sq.m</i>   | cu.m | 3,764.00  |           |        |
| 2.02              | Supply and place grouted riprap (5-20 kg rocks) for slope protection<br><i>at Pesos: _____ per cu.m</i>                 | cu.m | 1,460.00  |           |        |
| 2.03              | Supply and place 3,500 psi concrete for concrete facing, stair landing and RC curb<br><i>at Pesos: _____ per cu.m</i>   | cu.m | 1,062.00  |           |        |
| 2.04              | Supply and install steel reinforcement for concrete facing, stair landing and RC Curb<br><i>at Pesos: _____ per kg.</i> | kg   | 35,433.00 |           |        |

|                    |   |      |        |  |  |
|--------------------|---|------|--------|--|--|
| 2.05               | Supply, spread and compact Aggregate Base Course<br><br><i>at Pesos: _____ per cu.m</i>                     | cu.m | 153.00 |  |  |
| 2.06               | Supply and place Portland Cement Concrete Pavement (PCCP, 250mm thk)<br><br><i>at Pesos: _____ per sq.m</i> | sq.m | 732.00 |  |  |
| 2.07               | Supply and deliver to site Mooring Cleat (1T) including accessories<br><br><i>at Pesos: _____ per set</i>   | set  | 16.00  |  |  |
| 2.08               | Install Mooring Cleat (1T) including accessories<br><br><i>at Pesos: _____ per set</i>                      | set  | 16.00  |  |  |
| 2.09               | Excavate existing seabed up to required elevation<br><br><i>at Pesos: _____ per cu.m</i>                    | cu.m | 890.00 |  |  |
| <b>GRAND TOTAL</b> |   |      |        |  |  |

**TOTAL AMOUNT OF BID (INCLUSIVE OF VAT):**

\_\_\_\_\_  
(in words)

Submitted by:

Date: \_\_\_\_\_

\_\_\_\_\_  
Name & Signature of the Representative of the Bidder

\_\_\_\_\_  
Position

\_\_\_\_\_  
Name of the Bidder