

PROJECT FEATURE

PROJECT TITLE: ZAM 04-2017 (NRP-ZBO-05-17)

Repair of Damaged T-Head Pier (Landside) Slab, Curtain Wall and Curb including Mooring and Fendering System (Phase - II), Port of Zamboanga, Zamboanga City

ABC: Php28, 524,974.00, inclusive of 12% VAT

PROJECT DURATION: 190 Calendar Days

SCOPE OF WORK:

- I. Mobilization/Demobilization - 1.00 lot
- II. Installation of falseworks & clippings in preparation for demolition and disposal - 205.74 m²
- III. Demolition and Disposal - 185.15 m³
- IV. Reinforcement - 41,143.67 kgs
- V. Concrete works - 210.22 m³
- VI. Supply and Deliver of Rubber Dock Fenders (RDF) - 600H x 2000L V-Type - 24.00 set
- VII. Installation of Rubber Dock Fenders (RDF) - 24.00 set
- VIII. Supply and Deliver of 50-Tons Mooring Bollard - 10.00 set
- IX. Installation of 50-Tons Mooring Bollard - 10.00 set
- X. Construction Health and Safety Program - 190.00 c.d.

LAY OUT PLAN:



