

PROJECT FEATURE

PROJECT TITLE: ZAM 03-2017 (NRP-ZBO-03-17)

Proposed Repair of Damaged Rip-Rap at the Back of Admin Building, Port of Pagadian, TMO-Zamboanga Del Sur

ABC: Php14,404,562.00, inclusive of 12% VAT

PROJECT DURATION: 212 Calendar Days

SCOPE OF WORK:

- I Mobilization/Demobilization - 1.00 lot
- II Demolition of damaged Riprap - 611.04 cu.m
- III Supply & Place-in Underlayer Rocks (50-100 kgs) - 1,321.36 cu.m
- IV Supply & Place-in Core Rocks/Boulders (25-50 kgs) - 1,321.36 cu.m
- V L-Shape Retaining Wall - 66.38 lm
 - a Reinforcement - Item 404 - 8,032.88 kgs
 - b Concrete - Item 405 - 87.62 cu.m
- VI Supply and Place-in Rock Boulders (Core Quarry Run - CQR)- 249.29 cu.m
- VII Supply & Place-in Aggregate Subbase Course (Item 200) - 53.82 cu.m
- VIII Supply & Place-in Aggregate Base Course (Item 201) - 44.85 cu.m
- IX Supply and Place-in Portland Cement Concrete Pavement (PCCP) - Item 311 - 156.00 sqm
- X Grouted Rip-Rap - 82.23 lm
 - a Reinforcement - Item 404 - 5,102.37 kgs
 - b Concrete - Item 405 - 132.29 cu.m
- XI Repair/Provision of Dilapidated Fence - 68.73 lm
 - a Reinforcement - Item 404 -1,334.67 kgs
 - b Concrete - Item 405 - 4.45 cu.m
 - c Masonry Works - 61.86 sq.m
 - d Provision of Steel Matting Fence - 109.97 sq.m
- XII Construction Health and Safety Program - 212.00 c.d.

LAY OUT PLAN:

