Item No.	Description	Unit	Quantity		Unit Cost	Amount
I	**Mobilization and demobilization** Supply of Labor and Equipment for the Mobilization and Demobilization works Three Hundred Ninety Six Thousand Four Hundred Eighty pesos per lot	Lot	1.00		396,480.00	396,480.00
II	**Repair of PPA TMO Office** Supply of Labor, Materials and Equipment forthe Repair of TMO Office					
	a.) Repair of Roofing	Lot	1.00		131,783.34	131,783.34
	b.) Construction of Septic Vault	Lot	1.00		34,890.24	34,890.24
	c.) Repair of Ceiling	Lot	1.00		56,445.54	56,445.54
	d.) Plumbing Works	Lot	1.00		36,569.99	36,569.99
	e.) Electrical Works	Lot.	1.00		59,975.53	59,975.53
	f.) Finishing Works (Repair ofWalling)	Lot	1.00		33,304.32	33,304.32
	g.) Tile Works	Lot	1.00		58,467.58	58,467.58
	h.) Installation of Doors & Windows	Lot	1.00		72,688.00	72,688.00
	Four Hundred Eighty FourOne Hundred Twenty Four Pesos and Fifty Four Cents per lot					**484,124.54**
III	**Repair of Superstructure** Supply of Labor, Materials and Equipment for the Repair of Superstructure					
	a.) Demolition & Disposal of Existing RC Slabs Flooring, Curbs, Beams & Curtain Walls.	Cu.m.	196.00		2,384.27	467,316.92
	b.) Supply & Delivery of .40M.x.40M. PCP Piles (4,500 psi)	l.m.	232		4,853.46	1,126,002.72
	c.) Handle, Pitch & Drive .40M.x.40M. PSC Batter Piles	l.m.	232		3,896.44	903,974.08
	d.) Splicing of 9-Sets .40M. x.40M. RC Piles	set	9.00		19,824.00	178,416.00
	e.) Supply & Installation of Reinforcing Steel Bars	kg.	18,862.77		91.02	1,716,889.33
	f.) Concreting of Superstructure	cu.m.	162.61		14,818.73	2,409,673.69
	g.) Supply/Deliver 10 10-Units V500x1500 RDF	set	10		158,592.00	1,585,920.00
	h.) Installation of 10-Units V500x1500 RDF	set	10		9,330.50	93,305.00
	i.) Supply/Deliver of 8-Units 50T T-Head Mooring Bollard	unit	8		160,574.40	1,284,595.20
	j.) Installation of 8-Units 50T T-Head Mooring Bollard	unit	8		991.20	7,929.60
	Nine Million Seven Hundred Seventy Four Tousand Twenty Two Pesos and Fifty Four cents .					**9,774,022.54**
IV	**Repair of Damaged Rock Causeway** Supply of Labor, Materials and Equipment for the Repair of Damaged Rock Causeway.					

WITNESS:
RICHMON KNAT

ZET CONSTRUCTION
BY:
JUPI A. TAING
Owner/Manager

WITNESS:
BELTZASAR L. GELLA
Acting ESD Manager

Philippine Ports Authority:
BY:
ENGR. ASTERO C. GALLARDO, JR
Acting PortManager

	a.) Handling & Installation of Core Rock	Cu.m.	3,298.39	959.63	3,165,234.00
	b.) Handling & Installation of Armour Rock	Cu.m.	4,579.79	1,168.72	5,352,492.17
	c.) Installation of Geotextile Fabric	Sq.m.	547.62	410.00	224672.06
	d.) Spreading & Compaction of Selected Fill	Cu.m.	202.66	613.00	124,230.58
	e.) Spreading & Compaction of Aggregate Sub-Base Course	Cu.m.	105.85	741.64	78,502 59
	f.) Spreading & Compaction of Aggregate Base Course	Cu.m.	105.85	850.02	89,974.62
	g.) Spreading & Compaction of Gravel (Passing 3/4"Ø)	Cu.m.	105.85	2,774 30	293,659.66
	h.) Repair Concreting of Back-Up Area Abutment	Cu.m.	118.08	8,316.52	982,014.68
	i.) Grouting of Riprap	Cu.m.	59.20	4,263.95	252,425.84
	Ten Million Five Hundred Sixty Three Thousand Two Hundred Six Pesos and Twenty Cents				**10,563,206.20**
V	**Construction Safety & Health ProgramWorks** Supply of Labor, Materials and Equipment for Construction Safety & Health Program				
	Two Hundred Ten Thousand Sixty Eight Pesos and thirty Two Cents per lot	lot	1.00	210,068.32	**210,068.32**
				Total Cost of Bid >>>>>>>>>>>>>>>>	**P21,247,901.60**
	Twenty One Million Four Hundred Twenty Seven Thousand Nine Hundred One Pesos and Sixty Centavos Only				**P21,427,901.60**
	Amount in words				

WITNESS:
RICHMON KILAT

ZET CONSTRUCTION
By:
JULIO J. TALING
Owner/Manager

WITNESS:
BELTZASAR L. GELLA
Acting ESD Manager

Philippine Ports Authority:
By:
ENGR. ASTERIO C. GALLARDO, JR
Acting PortManager

2.02 The CONTRATOR agrees to commence, perform and complete the work called for and defined in this Contract at its sole cost and expense and to fully and faithfully furnish all materials, tools, labor, supplies, equipment, services and superintendence for the implementation of this contract in accordance with the schedule in the contract documents forming integral parts of this Contract.

2.03 The CONTRACTOR guarantees, among others, that all tools, equipment, machinery, instruments, accessories and materials it will supply or deliver or install and/or use in the construction and workmanship of all his work under the contract, shall be in accordance with the Contract Documents.