

**PHILIPPINE PORTS AUTHORITY**

Port Management Office - EASTERN LEYTE/SAMAR

Port of Tacloban, Port Area, Tacloban City

Telephone nos. (053) 321 - 1915; Fax No. (053) 325 - 7248

ESD E-Mail Address : [esd\\_pmotac@yahoo.com](mailto:esd_pmotac@yahoo.com)

Date : February 15, 2017

Ref. PR No. TAC-2330-17dated 16 Feb 2017**REQUEST FOR QUOTATION****Sir:**

Please quote your lowest price on the item(s) listed below. Do not quote more than one price on any single item, otherwise same shall be rejected at bid opening. Seal and return this form with your quotation not later than **March 03, 2017 at 10:00am Office of the Chairman, BAC-EP.**, Engineering Services Division. 3rd Floor, PMO -Bldg. Philippine Ports Authority, Port Area, Tacloban City. Please attach copy of the PPA Official Receipt in the amount of Five Hundred Sixty (Php 560.00) pesos as proof of payment of the non-refundable fee for the cost of Bidding documents.

Interested bidders are restricted to Filipino citizens / sole proprietorships, partnerships or organizations with at least seventy five percent (75%) interest or outstanding capital stock belonging to citizens of the Philippines.

Interested Bidders may secure Bid Documents from the BAC-EP TWG/ Secretariat at PPA PMO - Eastern Leyte/Samar, Port area, Tacloban City, upon payment of a non-refundable fee of Five Hundred Sixty (560.00) pesos only, inclusive of VAT.

  
**MARCELO C. INDIC**
**Chairman, PMO, BAC- EP**

Item No.	Work Description	Unit	Quantity	Unit Price
	Name and Location of Project :			
	<b>Concrete Overlay of Flooring of Covered Walk</b>			
	<b>Port of Manguino-o, Calbayog Samar</b>			
	<b>Port of Tacloban</b>			
	Approved Budget for the Contract : <b>PhP 496,037.00</b>			
	Project Duration : <b>33</b> Calendar Days			
	Brief Project Description/Scope of Work: ( <b>Please see Terms of Reference</b> )			
	( <b>LABOR, MATERIALS AND EQUIPMENT</b> )			
	<b>1.01 Masonry works:</b>			
	a) Concrete overlaying of flooring of pathwalk by 0.10m thk			
	x 2.10m width and 125.00m length of the entire covered walk area	cu.m.	34.50	
	b) Supply and install 0.025m x 1.00m G.I. steel grating (G.I. steel			
	drainage canal cover) as shown in the plan	unit	20	
	<b>2.01 Chipping Works:</b>			
	Chipping of portion of Concrete Pavement near the pedestrian to			
	the drain hole.			
	a) To lower the elevation of pavement to 0.10m thk x 0.15m width			
	and 16m in length from pedestrian gate to to the drain hole so			
	that stagnant rain waters can freely flow.	cu.m.	0.24	
	b) Chipping of every two (2) inner corners of of concrete columns			
	of covered walk structure which protrude at the pathwalk.			
	40 - 0.20m x 0.20m x 0.30m conc. Columns	pcs.	40	
	<b>3.01 Demolition Works:</b>			
	a) Demolition of unused septic tank which obstruct the			
	pathway of the covered walk. Area	cu.m.	0.5625	
	b) Restoration of demolished pavement	cu.m.	0.60	
	<b>TOTAL BID AMOUNT</b>		PhP	

  
**VICTOR ANSEL O. TINGZON**

BAC - Secretariat

Name of Supplier/Contractor