

PHILIPPINE PORTS AUTHORITY
 Port Management Office - EASTERN LEYTE/SAMAR
 Port of Tacloban, Port Area, Tacloban City
 Telephone nos. (053) 321 - 1915; Fax No. (053) 325 - 7248
 ESD E-Mail Address : esd pmotac@yahoo.com

Date : April 5,2017
 Ref. PR No. 2377
 dated March 29,2017

REQUEST FOR QUOTATION

Sir:
 Please quote your lowest price on the item(s) listed below. Do not quote more than one price on any single item, otherwise same shall be rejected at bid opening. Seal and return this form with your quotation not later than **May 2, 2017 at 10:00am to the Office of the Chairman, BAC-EP.** , Engineering Services Division. 3rd Floor, PMO -Bldg. Philippine Ports Authority, Port Area, Tacloban City. Please attach copy of the PPA Official Receipt in the amount of Five Hundred Sixty (Php 560.00) pesos as proof of payment of the non-refundable fee for the cost of Bidding documents.

Interested bidders are restricted to Filipino citizens / sole proprietorships, partnerships or organizations with at least seventy five percent (75%) interest or outstanding capital stock belonging to citizens of the Philippines Philippines

Interested Bidders may secure Bid Documents from the BAC-EP TWG/ Secretariat at PPA PMO - Eastern Leyte/Samar, Port area, Tacloban City, upon payment of a non-refundable fee of Five Hundred Sixty (560.00) pesos only, inclusive of VAT.


MARCELO C. INDIC
 Chairman, PMO, BAC- EP

| Item No. | Work Description | Unit | Quantity | Unit Cost | Amount |
|----------|--|-------|----------|-----------|--------|
| | Name and Location of Project : | | | | |
| | Repair of Admin. And Cashier's Offices of PMO-ELS building, Tacloban City | | | | |
| | Port of Tacloban | | | | |
| | Approved Budget for the Contract : PhP 470,390.17 | | | | |
| | Project Duration : 80 Calendar Days | | | | |
| | Brief Project Description/Scope of Work: (Please see Plans and Specifications) | | | | |
| | (LABOR, MATERIALS AND EQUIPMENT) | | | | |
| | Repair of Admin and Admin Stock Room | | | | |
| I | 1.0 Partition Wall | | | | |
| | 1.1.1 Supply and install 8" PVC panelling wall(double wall) on 2"x4" wall studs, and demolition of wallfor stock room doo, | sq.m. | 55.82 | | |
| | 1.2.1 Supply and install 1/4" thk. clear glass w/ super dark tint on 1m x 2m window,w/ anoloc aluminum frame and 2 sets hollow core doors. | sq.m. | 5.36 | | |
| | 2.0 Provision of comfort room | | | | |
| | 2.1 Water Supply and Drainage | | | | |
| | 2.1.1 Supply, install connect and restore to PMO building cold water lineand drainage line | lot | 1 | | |
| | 2.2 CHB wall | | | | |
| | 2.2.1 Supply and install CHB for C.R. | lot | 1 | | |
| | 2.3 Plumbing Fixtures | | | | |
| | 2.3.1 Supply and install plumbing fixtures | lot | 1 | | |
| | 2.4 Tile works | | | | |
| | 2.4.1 Supply and install selected floor and wall tiles | sq.m. | 10.46 | | |
| | 3.0 Painting works | | | | |
| | 3.1.1 Painting of hollow core doors, CHB conc wall and retouch Painting works | sq.m. | 22 | | |
| | 4.0 Electrical works | | | | |
| | 4.1.1 Supply and install 6 units down light and one unit power outlet at stock room | lot | 1 | | |

