



**REQUEST FOR QUOTATION  
(SMALL VALUE PROCUREMENT)  
ESD 2023-04-015**

The Philippine Ports Authority, PMO – Zamboanga Bids and Awards Committee now invites suppliers/contractors to submit price quotations for the **One (1) Lot Supply of labor, materials and equipment for the “Improvement of ESD Maintenance Workshop at Powerhouse Compound at Port of Zamboanga, Zamboanga City.**

Bids/Quotations received in excess of the **ABC (Php977,173.06)** shall be automatically rejected at Bid opening.

Procurement will be conducted in consonance with Section 53.9 (Small Value Procurement) of the Revised Implementing Rules and Regulations Part A (IRR-A) of Republic Act 9184 (R.A. 9184), otherwise known as the “Government Procurement Reform Act”. Only sealed bids/Quotations from **eligible bidders** will be opened and a contract will only be awarded to the Lowest Calculated Responsive Quotation.

The Opening of Sealed Quotation Envelopes shall be at **10:00 AM, May 22, 2023**, Conference Room, 2<sup>nd</sup> Floor PPA Administration Building, Port Area, Zamboanga City.

The PPA, PMO-Zamboanga reserves the right to reject any and all bids, declare a failure of bidding, or not award the contract at any time prior to contract award in accordance with Section 41 of RA 9184 and its IRR, without thereby incurring any liability to the affected bidder or bidders.

For further information, please refer to:

The TWG/Secretariat, PMO-ZAMBOANGA-BAC  
PPA, PMO-Zamboanga, Port Area, Zamboanga City 7000  
Tel Nos. (062) 991-2037, (062) 991-0650; Fax No. (062) 991-2360

**ARTHUR B. NOGAS**  
BAC Chairperson  
PPA, PMO-Zamboanga, Port Area, Zamboanga City 7000

PPA website: [www.ppa.com.ph](http://www.ppa.com.ph)  
PhilGEPS Website: [www.philgeps.net](http://www.philgeps.net)  
Date of Publication: May 15, 2023 to May 22, 2023

Project No.: SVP-01-2023  
PR Nos.: ZAM-103-2023(M)  
Canvass Ref.: ESD 2023-04-015

Encl.:

- Canvass Form
- Approved Agency Estimate

PORT MANAGEMENT OFFICE – ZAMBOANGA  
R.T. Lim Boulevard, Zamboanga City 7000, Philippines  
PO Box No. 360 Tel. Nos. (062) 991-2037 to 2039; 991-0650 TeleFax (062) 991-2360;  
Email : [ppa.pmozamboanga@gmail.com](mailto:ppa.pmozamboanga@gmail.com)/[pmozamboanga@ppa.com.ph](mailto:pmozamboanga@ppa.com.ph) website: [www.ppa.com.ph](http://www.ppa.com.ph)



**CANVASS FORM**

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
(Supplier)

Date:

JO/PR Number:

\_\_\_\_\_  
ZAM-103-2023(M)  
\_\_\_\_\_

Gentlemen: Please quote your government price/s for the article/s listed hereunder:

Item No.	Qty	Unit	Articles	Unit Cost	Amount
I	118.04	m <sup>2</sup>	<b>Removal and Disposal Works</b> <ul style="list-style-type: none"> <li>Supply of labor, tools/equipment for the removal and disposal of existing dilapidated structures.</li> <li>Supply of manpower, equipment &amp; tools for the removal and hauling to temporary laydown area of existing installed paving blocks.</li> </ul>		
II	58.88	m <sup>3</sup>	<b>Earth Works</b> <ul style="list-style-type: none"> <li>Supply of labor and tools/equipment for the excavation of footing-column.</li> <li>Supply of labor and tools/equipment for the footing-column gravel bedding.</li> <li>Supply of labor and tools/equipment for the backfilling of footing-column surrounds.</li> <li>Supply of labor and tools/equipment for the compaction of footing-column surrounds.</li> </ul>		
III	6.48	m <sup>3</sup>	<b>Concrete Works</b> <ul style="list-style-type: none"> <li>Supply of labor, materials, and tools/equipment for the fabrication of concrete mixing board platform.</li> <li>Supply of labor, materials and tools/equipment for the mixing and disposition of concrete for footing-column, column, beam, slab on grade, lintel beam, and wall footing.</li> <li>Supply of labor, materials, and tools/equipment for the rectification of minor concrete deficiency/honeycomb.</li> <li>Supply of labor, material and tools for the fabrication and installation of column, beam, and lintel beam.</li> <li>Supply of labor, material and tools for the fabrication and installation of shoring for forms and falseworks.</li> <li>Supply of labor, material and tools for the removal and stripping-off of shoring, forms and falseworks.</li> <li>Supply of labor, materials and tools/equipment for the fabrication and installation of reinforcement bars for footing-column, column, beam, slab on grade and Wall footing.</li> </ul>		
IV	1	Lot	<b>Electrical Works</b> <ul style="list-style-type: none"> <li>Supply of labor, materials, and Tools for the Installation of Electrical Rough-Ins; PVC, IMT, EMT, &amp; RSC Conduits.</li> <li>Supply of Labor, Materials and Tools for the Installation of Electrical Boxes, Pull boxes, Switch Boxes &amp; Junction Boxes.</li> <li>Supply of Labor, Materials and Tools for the Installation of Electrical Wires &amp; Cables.</li> <li>Supply of Labor, Materials and Tools for the Installation of Electrical Switches, Convenience Outlet &amp; Exhaust Fan</li> <li>Supply of Labor, Materials and Tools for the Installation of Electrical Lighting Fixtures</li> </ul>		


V	6.93	m <sup>2</sup>	Doors <ul style="list-style-type: none"> <li>• Supply and Delivery of Wooden Panel Doors including Accessories.</li> <li>• Supply of Labor and Tools for the Installation of Wooden Panel Doors and Accessories</li> </ul>		
VI	124.50	m <sup>2</sup>	Masonry <ul style="list-style-type: none"> <li>• Supply of labor, materials, and tools/equipment for the construction of 100mm CHB Wall including Reinforcement.</li> <li>• Supply of labor, materials and tools/equipment for the application of cement plaster finish.</li> <li>• Supply of Labor, Materials and Tools/Equipment for the Application of Masonry Wall Painting Works</li> </ul>		
VII	13.69	m <sup>2</sup>	Ceiling Works <ul style="list-style-type: none"> <li>• Supply and Delivery of Materials for the Fiber Cement Board on Metal Frame Ceiling</li> <li>• Supply of Labor, Materials and Tools/Equipment for the Application of Ceiling Painting Works</li> </ul>		
VIII	118.04	m <sup>2</sup>	Roofing Works <ul style="list-style-type: none"> <li>• Supply of labor, materials and tools/equipment for the fabrication, installation and framing of steel roof trusses.</li> <li>• Supply of labor, materials, and tools for the application of metal paint.</li> <li>• Supply of labor, materials, and tools/equipment for the installation of pre-painted metal roofing sheet.</li> <li>• Supply of labor, materials, and tools/equipment for the installation of roof accessories: End Flashing &amp; Fascia Cover.</li> </ul>		
			<i>x-x-x-Nothing Follows-x-x-x</i>		

Terms and Conditions:

1. Term of Payment – 100% Payment upon completion;
2. Project Duration - 73 Calendar Days;
3. Performance Security – in accordance with schedule provided under Section 39.2 of RA 9184;
4. Warranty: One (1) year after acceptance;
5. Quotation should be submitted in a sealed envelope.
<i>X X X Nothing Follows X X X</i>

Please submit your sealed quotation envelope on or before: **10:00 AM, May 22, 2023.**

  
**JASON LANCE V. SANTILLAN**  
 Canvasser

Very truly yours,  
  
**TASHMA H. ASID-MAADIL**  
 Acting ESD Manager

The above price/s and/or quotation/s for the article/s you wish to purchase/repair is/are available within \_\_\_\_\_ from the date of quotation.

\_\_\_\_\_  
**AUTHORIZED SIGNATURE**

\_\_\_\_\_  
 Name of Supplier/Firm/Company  
 Date:



### APPROVED AGENCY ESTIMATES

**Project:** One (1) Lot Supply of labor, materials, and equipment for the "Improvement of ESD Maintenance Workshop at Powerhouse Compound" at Port of Zamboanga, Zamboanga City.

**Location:** Port of Zamboanga, Zamboanga City

**Owner:** Zamboanga City

**Subject:** "Improvement of ESD Maintenance Workshop at Powerhouse Compound"

Item	Description	Unit	Qty.	Unit Cost	Amount
<b>Scope of Work:</b>					
Supply of labor, materials, and equipment for the "Improvement of ESD Maintenance Workshop at Powerhouse Compound"					
<ul style="list-style-type: none"> <li>• Supply of labor, tools/equipment for the removal and disposal of existing dilapidated structures.</li> <li>• Supply of manpower, equipment &amp; tools for the removal and hauling to temporary laydown area of existing installed paving blocks.</li> <li>• Supply of labor and tools/equipment for the excavation of footing-column.</li> <li>• Supply of labor and tools/equipment for the footing-column gravel bedding.</li> <li>• Supply of labor and tools/equipment for the backfilling of footing-column surrounds.</li> <li>• Supply of labor and tools/equipment for the compaction of footing-column surrounds.</li> <li>• Supply of labor, materials, and tools/equipment for the fabrication of concrete mixing board platform.</li> <li>• Supply of labor, materials and tools/equipment for the mixing and disposition of concrete for footing-column, column, beam, slab on grade, lintel beam, and wall footing.</li> <li>• Supply of labor, materials, and tools/equipment for the rectification of minor concrete deficiency/honeycomb.</li> <li>• Supply of labor, material and tools for the fabrication and installation of column, beam, and lintel beam.</li> <li>• Supply of labor, material and tools for the fabrication and installation of shoring for forms and falseworks.</li> <li>• Supply of labor, material and tools for the removal and stripping-off of shoring, forms and falseworks.</li> <li>• Supply of labor, materials and tools/equipment for the fabrication and installation of reinforcement bars for footing-column, column, beam, slab on grade and Wall footing.</li> <li>• Supply of labor, materials, and Tools for the Installation of Electrical Rough-Ins; PVC, IMT, EMT, &amp; RSC Conduits.</li> <li>• Supply of Labor, Materials and Tools for the Installation of Electrical Boxes, Pull boxes, Switch Boxes &amp; Junction Boxes.</li> <li>• Supply of Labor, Materials and Tools for the Installation of Electrical Wires &amp; Cables.</li> <li>• Supply of Labor, Materials and Tools for the Installation of Electrical Switches, Convenience Outlet &amp; Exhaust Fan</li> <li>• Supply of Labor, Materials and Tools for the Installation of Electrical Lighting Fixtures</li> <li>• Supply and Delivery of Wooden Panel Doors including Accessories.</li> <li>• Supply of Labor and Tools for the Installation of Wooden Panel Doors and Accessories</li> <li>• Supply of labor, materials, and tools/equipment for the construction of 100mm CHB Wall including Reinforcement.</li> <li>• Supply of labor, materials, and tools/equipment for the application of cement plaster finish.</li> <li>• Supply of Labor, Materials and Tools/Equipment for the Application of Masonry Wall Painting Works</li> <li>• Supply and Delivery of Materials for the Fiber Cement Board on Metal Frame Ceiling</li> <li>• Supply of Labor, Materials and Tools/Equipment for the Application of Ceiling Painting Works</li> <li>• Supply of labor, materials and tools/equipment for the fabrication, installation and framing of steel roof trusses.</li> <li>• Supply of labor, materials, and tools for the application of metal paint.</li> <li>• Supply of labor, materials, and tools/equipment for the installation of pre-painted metal roofing sheet.</li> <li>• Supply of labor, materials, and tools/equipment for the installation of roof accessories: End Flashing &amp; Fascia Cover.</li> </ul>					
<b>Materials:</b>					
1	Shovel	Pcs.	2		
2	Digging Hand Tools	Pcs.	2		
3	Gravel Bedding (G1)	m <sup>3</sup>	2		
4	40 Kgs. Portland Cement	Bags	113		
5	Coarse Aggregate G-1	m <sup>3</sup>	6		

6	Fine Aggregate S-1	m <sup>3</sup>	3		
7	50mm (2") X 50mm (2") X 8" Lumber	Pcs.	3		
8	6.35mm (1/4" X 1.2m X 2.4m Marine Plywood	Pc.	1		
9	50mm (2") X 50mm (2") X 10" Coco Lumber	Pcs.	110		
10	50mm (2") X 75mm (3") X 10" Coco Lumber	Pcs.	49		
11	12.5mm (1/2") X 1.2m X 2.4m Marine Plywood	Pcs.	30		
12	Reinforcing Steel Bars Deformed Grade 40	Kgs.	831		
13	# 16 GI Tie Wire	Kgs.	14		
14	20mmØ PVC Conduit	m	351		
15	20mmØ Corrugated Plastic Conduit	m	28		
16	6x6x4 PVC Pull box	Pcs.	5		
17	PVC Junction Box	Pcs.	46		
18	Utility Box	Pcs.	20		
19	2.0mm <sup>2</sup> THHN Wire	m	60		
20	3.5mm <sup>2</sup> THHN Wire	m	756		
21	5.5mm <sup>2</sup> THHN Wire	m	90		
22	2-Gang Universal Convenience Outlet w/ Ground, Flush Type	Assy.	9		
23	Special Purpose Outlet	Assy.	1		
24	1-Gang Switch, Recess Type	Assy.	2		
25	2-Gang Switch, Recess Type	Assy.	7		
26	3-Gang Switch, Recess Type	Assy.	1		
27	Duplex 18watts LED Lamp w/ Aluminum Reflector Fixture	Assy.	11		
28	18watts LED Lamp, w/ Prismatic Fixture	Assy.	3		
29	Wooden Panel Door (0.80m X 2.10m)	Unit	3		
30	Wooden Panel Door (0.90m X 2.10m)	Unit	1		
31	Hinges	Pcs.	12		
32	Lockset	Pcs.	4		
33	Wash Sand	m <sup>3</sup>	5		
34	4" (100mm) Concrete Hollow Blocks	Pcs.	1,335		
35	4" (100mm) Concrete Louver Blocks	Pcs.	285		
36	Pozzolan Cement (40 Kgs.)	Bags	68		
37	Fine Sand	m <sup>3</sup>	6		
38	Patching Compound (Polyester Body Filler)	Gals.	12		
39	Primer Paint (Flat Latex)	Gals.	10		
40	Topcoat (2 Coats Latex)	Gals.	10		
41	5mm X 4' X 8' Fiber Cement Board	Pcs.	5		
42	Single Metal Furring X 5m Length	Pcs.	16		
43	Double Metal Furring X 5m Length (For Carrying Channel)	Pcs.	5		



44	Carrying Channels X 5m Length (For Hanger)	Pcs.	14		
45	1" X 3m Wall Angle	Pcs.	4		
46	Blind Rivets	Pcs.	20		
47	Metal Screw	Pcs.	6		
48	4.76 mm Thick 3/16" X 2 1/2"(63.5mm) X 2 1/2"(63.5mm) X Angle Bar X 6.0m	Kgs.	340		
49	4.76 mm Thick 3/16" X 2"(50mm) X 2"(50mm) X Angle Bar	Kgs.	722		
50	'3/16" (5mm) Thk. Gusset Plate	Kgs.	54		
51	'50m X 75mm GA 12 C-Purlins	Kgs.	30		
52	'Welding Rod	Kgs.	23		
53	'Oxygen	Kgs.	253		
54	'Acetylene	Kgs.	13		
55	Red Oxide Primer	Gals.	2		
56	Enamel Paint	Gals.	9		
57	Paint Thinner	Gals.	6		
58	(0.20mm-0.60mm) 1040mm X 5m Long Span	Pcs.	15		
59	(0.20mm-0.60mm) 1040mm X 8.5m Long Span	Pcs.	15		
60	Tek Screw/J-bolt with washers	Pcs.	1,155		
61	End Flashings	m	36		
62	Fascia Cover/Board	m	30		
63	Blind Rivets	Pcs.	1,190		
X X X Nothing Follows X X X					
A	MATERIAL COST				
B	LABOR COST				
C	EQUIPMENT COST				
D	DIRECT COST; [(A) + (B) + (C)]				
E	OCM [15% OF (D)]				
F	PROFIT [Up to 10% OF (D)]				
G	5% VAT OF [(D)+(E)+(F)]				
H	TOTAL PROJECT COST; [(D) + (E) + (F) + (G)]				<u>≤Php977,173.06</u>