



## **REQUEST FOR QUOTATION (SMALL VALUE PROCUREMENT)**

The Philippine Ports Authority, PMO–Zamboanga, Bids and Awards Committee for Engineering Projects now invites suppliers/contractors to submit price quotations for the **Supply of labor, materials and materials for “Proposed Provision of Guardhouse at Main Gate Complex Approach” at Port of Zamboanga, Zamboanga City.**

Bids/Quotations received in excess of the **ABC (Php988,342.74)** shall be automatically rejected at Bid opening.

Procurement will be conducted in consonance with Section 53.9 (Small Value Procurement) of the Revised Implementing Rules and Regulations Part A (IRR-A) of Republic Act 9184 (R.A. 9184), otherwise known as the “Government Procurement Reform Act”. Only sealed bids/Quotations from **eligible bidders** will be opened and a contract will only be awarded to the Lowest Calculated Responsive Quotation.

The Opening of Sealed Quotation Envelopes shall be at **10:00 AM, September 13, 2022**, Conference Room, 2<sup>nd</sup> Floor PPA Administration Building, Port Area, Zamboanga City.

The PPA, PMO-Zamboanga reserves the right to reject any and all bids, declare a failure of bidding, or not award the contract at any time prior to contract award in accordance with Section 41 of RA 9184 and its IRR, without thereby incurring any liability to the affected bidder or bidders.

For further information, please refer to:

The TWG/Secretariat, PMO-ZAMBOANGA-BAC  
PPA, PMO-Zamboanga, Port Area, Zamboanga City 7000  
Tel Nos. (062) 991-2037, (062) 991-0650; Fax No. (062) 991-2360

**ARTHUR B. NOGAS**  
BAC Chairperson  
PPA, PMO-Zamboanga, Port Area, Zamboanga City 7000

PPA website: [www.ppa.com.ph](http://www.ppa.com.ph)

PhilGEPS Website: [www.philgeps.net](http://www.philgeps.net)

Date of Publication: September 5 - 12, 2022

Encl.: Canvass Form and Approved Agency Estimate

## CANVASS FORM

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
(Supplier)

Date:

JO/PR Number: ZAM-228-22 (M)

Gentlemen: Please quote your government price/s for the article/s listed hereunder:

| Item No.                                                                                                                                                                            | Qty    | Unit           | Articles                                                                                                                                                                                                                                                                                                                                                    | Unit Cost | Amount |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|----------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------|--------|
| <b>Scope of Works:</b><br><b>SUPPLY OF LABOR, MATERIALS AND EQUIPMENT FOR "PROPOSED PROVISION OF GUARDHOUSE AT MAIN GATE COMPLEX APPROACH AT PORT OF ZAMBOANGA, ZAMBOANGA CITY"</b> |        |                |                                                                                                                                                                                                                                                                                                                                                             |           |        |
| I                                                                                                                                                                                   | 1      | Lot            | <b>DEMOLITON AND DISPOSAL WORKS (EXISTING GUARDHOUSE)</b><br>a. Supply of labor, materials and equipment for Demolition and Disposal of Existing Guard House.                                                                                                                                                                                               |           |        |
| II                                                                                                                                                                                  | 2.91   | m <sup>3</sup> | <b>EXCAVATION WORKS</b><br>a. Supply of Labor, Materials and tools for Excavation of 2 units Column-Footing.                                                                                                                                                                                                                                                |           |        |
| III                                                                                                                                                                                 | 0.84   | m <sup>3</sup> | <b>CONCRETE WORKS</b><br>a. Supply of material and labor & place 0.10m Gravel bedding for 2 units Footing.<br>b. Supply Labor, Material and Equipment for Fabrication and Installation of Reinforcing Steel Bar for Footing, Column and Slab on Fill.<br>c. Supply of labor, materials and equipment for concrete works (Footing, Column and Slab on Fill). |           |        |
| IV                                                                                                                                                                                  | 46.10  | m <sup>2</sup> | <b>MASONRY WORKS</b><br>a. Supply of labor, materials and equipment for supply & placement of 100mm thk CHB (Including Reinforcement).<br>b. Supply of labor, materials and tools for Cement Plaster Finish of column and CHB wall.                                                                                                                         |           |        |
| V                                                                                                                                                                                   | 896.64 | Kgs.           | <b>STEEL WORKS</b><br>a. Supply of Labor, Materials, and Equipment for Fabrication and Installation of Structural Steel for (Columns, Roof Beam & Canopy).<br>b. Supply of Labor, Materials, and Equipment for Fabrication and                                                                                                                              |           |        |

PORT MANAGEMENT OFFICE - ZAMBOANGA

R.T. Lim Boulevard, Zamboanga City 7000, Philippines

PO Box No. 360 Tel. Nos. (062) 991-2037 to 2039; 991-0650 TeleFax (062) 991-2360;

Email : [ppa.pmozamboanga@gmail.com](mailto:ppa.pmozamboanga@gmail.com)/pmozamboanga@ppa.com.ph website: [www.ppa.com.ph](http://www.ppa.com.ph)

|      |        |                |                                                                                                                                                                                                                                                                                                                                             |  |  |
|------|--------|----------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--|--|
|      |        |                | Installation of Structural Steel for (Roof Truss).<br>c. Supply of Labor, Materials and Equipment for Fabrication and Installation of Steel Purlins.<br>d. Supply of Labor and Materials for installation of Steel Plates.                                                                                                                  |  |  |
| VI   | 51.58  | m <sup>2</sup> | <b>ROOFING WORKS</b><br><br>a. Supply of labor, materials and equipment for installation of Corrugated Metal roofing.<br>b. Supply of labor, materials and equipment for installation of Fabricated Metal Roofing Accessories (Gutter with Flashing).<br>c. Supply of Labor and Materials for Installation of Double Sided Insulation Foam. |  |  |
| VII  | 32.70  | m <sup>2</sup> | <b>TILLING WORKS</b><br><br>a. Supply of Labor and Materials for Fabrication and Installation of Marine Plywood on Steel Framing Flooring.<br>b. Supply of Labor and Materials for Installation of Unglazed Ceramic Tiles.<br>c. Supply of Labor and Materials for Installation of Vinyl Tiles.                                             |  |  |
| VIII | 32.28  | m <sup>2</sup> | <b>CARPENTRY WORKS</b><br><br>a. Supply of Labor and Materials for Installation of Fiber Cement Board on Metal Frame Double Wall.<br>b. Supply of Labor and Materials for Installation of Double-Sided Insulation Foam.<br>c. Supply of Labor and Materials for Installation of Double-Sided Insulation Foam.                               |  |  |
| IX   | 80.68  | m <sup>2</sup> | <b>CEILING WORKS</b><br>a. Supply of Labor and Materials for Installation of Fiber Cement Board on Metal Frame Ceiling.                                                                                                                                                                                                                     |  |  |
| X    | 12.23  | m <sup>2</sup> | <b>DOORS &amp; WINDOWS</b><br><br>a. Supply of Labor and Materials for Installation of Doors and Windows.                                                                                                                                                                                                                                   |  |  |
| XI   | 224.47 | m <sup>2</sup> | <b>PAINTING WORKS</b><br><br>a. Supply of Labor and Materials for Painting of wood surface.<br>b. Supply of Labor and Materials for Painting of Masonry surface.<br>c. Supply of Labor and Materials for Painting of Metal surface.                                                                                                         |  |  |
| XII  | 1      | Lot            | <b>PLUMBING WORKS</b><br><br>a. Supply Labor and Materials for installation of Sanitary pipes, Lavatory and Water Closet.                                                                                                                                                                                                                   |  |  |

|      |   |     |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |  |  |
|------|---|-----|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--|--|
| XIII | 1 | Lot | <b>ELECTRICAL WORKS</b> <ol style="list-style-type: none"> <li>Supply of Labor, Materials and Tools for the Installation of Electrical Rough-Ins; PVC, IMT, EMT, &amp; RSC Conduits.</li> <li>Supply of Labor, Materials and Tools for the Installation of Electrical Wires &amp; Cables.</li> <li>Supply of Labor, Materials and Tools for the Installation of Electrical Lighting Fixtures.</li> <li>Supply of Labor, Materials and Tools for the Installation of Electrical Switches, Convenience Outlet &amp; Exhaust Fan.</li> <li>Supply of Labor, Materials and Tools for the Installation of Electrical Boxes, Pull boxes, Switch Boxes &amp; Junction Boxes.</li> <li>Electrical Circuit Protections &amp; Electric Meter.</li> </ol> |  |  |
|      |   |     | <i>x-x-x-Nothing Follows-x-x-x</i>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |  |  |

Terms and Conditions:

|                                                                                                           |
|-----------------------------------------------------------------------------------------------------------|
| 1. Term of Payment – 100% Payment upon completion                                                         |
| 2. Project Duration - 65 Calendar Days;                                                                   |
| 3. Performance Security - in accordance with schedule provided under Sect. 39.2 of RA 9184;               |
| 4. Warranty: One (1) year after acceptance;                                                               |
| 5. Quotations should be submitted in a sealed envelope;                                                   |
| 6. Please submit your sealed quotation envelope on or before: <b><u>10:00 AM, September 13, 2022.</u></b> |
| 7. Detailed breakdown of Bill of Quantities.                                                              |
| X X X Nothing Follows X X X                                                                               |

Very truly yours,

JASON LANCE V. SANTILLAN  
Canvasser

JOHNSON D. KHO  
ESD Manager

The above price/s and/or quotation/s for the article/s you wish to purchase/repair is/are available within \_\_\_\_\_ days from the date of quotation.

AUTHORIZED SIGNATURE

Name of Supplier/Firm/Company

Date: Quoted:

### APPROVED AGENCY ESTIMATES

**Project:** SUPPLY OF LABOR, MATERIALS AND EQUIPMENT FOR "PROPOSED PROVISION OF GUARDHOUSE AT MAIN GATE COMPLEX APPROACH AT PORT OF ZAMBOANGA, ZAMBOANGA CITY"

**Location:** Port of Zamboanga, Zamboanga City

**Responsible Center:** PMO- Zamboanga

**Subject:** Bill of Quantities and Materials.

| Item                                                          | Description                                         | Unit           | Qty.   | Unit Cost | Amount |
|---------------------------------------------------------------|-----------------------------------------------------|----------------|--------|-----------|--------|
| <b>Scope of Works:</b>                                        |                                                     |                |        |           |        |
| I                                                             | DEMOLITON AND DISPOSAL WORKS (EXISITING GUARDHOUSE) | Lot            | 1      |           |        |
| II                                                            | EXCAVATION WORKS                                    | m <sup>3</sup> | 2.91   |           |        |
| III                                                           | CONCRETE WORKS                                      | m <sup>3</sup> | 0.84   |           |        |
| IV                                                            | MASONRY WORKS                                       | m <sup>2</sup> | 46.10  |           |        |
| V                                                             | STEEL WORKS                                         | Kgs.           | 896.64 |           |        |
| VI                                                            | ROOFING WORKS                                       | m <sup>2</sup> | 51.58  |           |        |
| VII                                                           | TILLING WORKS                                       | m <sup>2</sup> | 32.7   |           |        |
| VIII                                                          | CARPENTRY WORKS                                     | m <sup>2</sup> | 32.28  |           |        |
| IX                                                            | CEILING WORKS                                       | m <sup>2</sup> | 80.68  |           |        |
| X                                                             | DOORS & WINDOWS                                     | m <sup>2</sup> | 12.23  |           |        |
| XI                                                            | PAINTING WORKS                                      | m <sup>2</sup> | 224.4  |           |        |
| XII                                                           | PLUMBING WORKS                                      | Lot            | 1      |           |        |
| XIII                                                          | ELECTRICAL WORKS                                    | Lot            | 1      |           |        |
| <b>Materials:</b>                                             |                                                     |                |        |           |        |
| <u>I. DEMOLITON AND DISPOSAL WORKS (EXISITING GUARDHOUSE)</u> |                                                     |                |        |           |        |
| Chisel (Moil) – 3 Pcs.                                        |                                                     |                |        |           |        |
| Steel Mallet (Heavy Duty) – 3 Pcs.                            |                                                     |                |        |           |        |
| <u>II. EXCAVATION WORKS</u>                                   |                                                     |                |        |           |        |
| Shovel – 2 Pcs.                                               |                                                     |                |        |           |        |
| Digging Hand Tools – 2 Pcs.                                   |                                                     |                |        |           |        |
| <u>III. CONCRETE WORKS</u>                                    |                                                     |                |        |           |        |
| Gravel Bedding (G1) – 0.25 m3                                 |                                                     |                |        |           |        |
| Reinforcing Steel Bars Deformed Grade 40 – 33 Kgs.            |                                                     |                |        |           |        |
| # 16 GI Tie Wire – 1 Kgs.                                     |                                                     |                |        |           |        |
| Good Lumber – 59 Bd Ft                                        |                                                     |                |        |           |        |
| 1/2" thk Marine Plywood – 2 Pcs.                              |                                                     |                |        |           |        |
| C.W. Nails – 1 Kgs.                                           |                                                     |                |        |           |        |
| Portland Cement (Type 1) – 8 Bags                             |                                                     |                |        |           |        |
| Coarse Aggregates (G-1) – 1 m3                                |                                                     |                |        |           |        |
| Gravel (G-1) – 1 m3                                           |                                                     |                |        |           |        |

Water @ 0.40 Water/Cement Ratio  
50mm (2") X 50mm (2") X 8" Lumber – 3 Pcs.  
1/2" thk Marine Plywood – 1 Pcs.

#### IV. MASONRY WORKS

100mm thk CHB – 289 Pcs.  
Portland Cement (Type 1) – 20 Bags  
Wash Sand – 1 m3  
Reinforcing Steel Bars Deformed Grade 40 – 73 Kgs.  
# 16 GI Tie Wire – 2 Kgs.  
Fine Aggregates (Sand) – 1 m3

#### V. Steel Works

G.I. Square Tube (4" X 2.5mm thk) – 6 Pcs.  
G.I. Rectangular Tube (2" X 3" X 1.5mm thk) – 5 Pcs.  
G.I. Rectangular Tube (2" X 3" X 1.2mm thk) – 3 Pcs.  
6mm thk X 38mm X 38mm Angle Bar – 16 Pcs.  
C-Purlins (2" X 3" X 1.0mm thk)  
Steel Plate (Milled Checkered fy36) – 38 Kgs.  
Expansion Bolt 5" X 5/8" – 42 Pcs.  
Acetylene – 9 Kgs.  
Oxygen – 17 Kgs.  
Welding Rod – 18 Kgs.

#### VI. Roofing Works

Corrugated Roofing, GA 26 (0.551mm X 2.44m) – 55 m2  
Tek Screw/J-Bolt with Washer – 550 Pcs.  
G.I. Sheet Plain GA24 X 8' (0.955mm thk) -12 Pcs.  
Blind Rivets – 215 Pcs.  
Reflective Double-Sided Insulation 1m X 20mm thk – 1 Roll

#### VII. Tilling Works

G.I. Rectangular Tube (2" X 4" X 2.5mm thk) – 6 Pcs.  
G.I. Square Tube (2" X 4" X 2.5mm thk) – 5 Pcs.  
3/4" thk X 4" x 8" Marine Plywood – 3 Pcs.  
Acetylene – 2 Kgs.  
Oxygen – 4 Kgs.  
Welding Rod – 3 Kgs.  
Unglazed Ceramic Tiles – 13.50 m3  
Portland Cement (Type 1) – 5 Bags  
Fine Aggregates (Sand) – 3 m3  
Tile Grout – 2 Bags  
Vinyl Tiles – 10.50 m2  
Glue Adhesive – 5 Liters

#### VIII. Carpentry Works

Fiber Cement Board (4' X 8' X 9mm thk) – 12 Pcs.  
Fiber Cement Board (4' X 8' X 4.5mm thk) – 11 Pcs.  
Metal Stud (35mm X 76mm X 3m) – 29 Pcs.  
Base Board 4" X 8" 1" thk – 9 Pcs.  
Blind Rivets – 3,398 Pcs.  
1" Metal Screw – 130 Pcs  
Door Jamb (Good Lumber) – 2 Set  
Reflective Double-Sided Insulation 1m X 20mm thk – 1 Roll

#### IX. Ceiling Works

Fiber Cement Board (4' X 8' X 3.5mm thk) – 29 Pcs.  
Metal Furring Double – 92 Pcs.  
Carrying Channel – 29 Pcs.  
Channel Clip – 485 Pcs.  
Hanger Bar/Rod – 81 Pcs.  
Wall Angle – 20 Pcs.  
Blind Rivets – 1,130 Pcs.  
1" Metal Screw – 323 Pcs

X. Doors & Windows

Solid Panel Door  
PVC Door w/ Jamb and Louver  
Door Lock  
Door Knob  
Fixed Clear Glass Window on Analok Framing (120 X 210) – 2 Pcs.  
Sliding Clear Glass Window on Analok Framing (80 X 120) – 2 Pcs.  
Sliding Clear Glass Window on Analok Framing (110 X 40) – 1 Pcs.

XI. Painting Works

Glazing Putty – 7 Gal.  
Flatwall Enamel – 6 Gal.  
Quick Dry Enamel – 6 Gal.  
Paint Thinner – 4 Lit.  
Tinting Color – 2 Lit.  
Concrete Neutralizer – 1 Gal.  
Concrete Sealer/Primer – 1 Gal.  
Patching Compound – 1 Gal.  
Semi-Gloss Latex - 4 Lit.  
Red Oxide Primer – 3 Gal.  
Paint Enamel – 7 Gal.  
Paint Thinner – 17 Lit.  
Tinting Color – 1 tin

XII. Plumbing Works

Water Closet Including Fittings & acc. (round) American std or equivalent – 1 Pc.  
Lavatory including fittings & acc. American std or equivalent – 1 Pc.  
PVC Pipe (100mm X Ø 3m) – 7 Pcs.  
PVC Pipe (50mm X Ø 3m) – 2 Pcs.  
PVC Pipe Wye (100mm Ø) – 2 Pcs.  
PVC Pipe Wye (50mm Ø) – 2 Pcs.  
PVC Elbow 90 (100mm Ø) – 12 Pcs.  
Clean Out Set 100mm – 2 Pcs.  
Tee Reducer 100mm x 50mm – 2 Pcs.

XIII. Electrical Works

20mm Thck Wall PVC Conduit – 66 m  
32mmØ PVC Conduit – 85 m  
20mm Corrugated Flexible Conduit – 18 m  
2.0mm THHN Wire –75 m  
3.5mm THHN Wire – 31 m  
5.5mm THHN Wire – 10 m  
14mm THHN Wire – 200 m  
2.0mm TW Wire (Ground Wire) – 74 m  
8.0mm TW Wire (Ground Wire) – 85 m  
13Watts LED Slim Downlight, Recess – 9 Assy.  
1-Gang Switch, Flush Type – 2 Assy.  
Three-Gang Switch – 3 Assy.  
Ground Fault Circuit Interrupter Convenience Outlet – 2 Assy.  
2-Gang Universal Convenience Outlet w/ Ground, Flush Type – 4 Assy.  
Special Purpose Outlet – 1 Assy.  
4x4x2 PVC Pull box – 4 Pcs.  
PVC Junction Box – 28 Pcs.  
Utility Box – 12 Pcs.  
Panelboard (Center Main : 40AT/50AF/10KAIC/2P/230V MCCB, Bolt-On Type; 4 Branches; 1-unit 15AT/50AF/10KAIC/2P/230 MCCB, Bolt-On Type; 2-unit 20AT/50AF/10KAIC/2P/230 MCCB, Bolt-On Type); 1unit- 30AT/50AF/10KAIC/2P/230 MCCB Bolt-On Type; With 6 Ground Terminals – 1 Assy.  
Electric Meter 230V/100 amps/2P with Meter Base – 1 Unit

X X X Nothing Follows X X X

|   |                |  |  |  |  |
|---|----------------|--|--|--|--|
| A | MATERIAL COST  |  |  |  |  |
| B | LABOR COST     |  |  |  |  |
| C | EQUIPMENT COST |  |  |  |  |

|   |                                             |  |  |  |                       |
|---|---------------------------------------------|--|--|--|-----------------------|
| D | DIRECT COST; [(A) + (B) + (C)]              |  |  |  |                       |
| E | OCM [Up to 15% OF (D)]                      |  |  |  |                       |
| F | PROFIT [Up to 10% OF (D)]                   |  |  |  |                       |
| G | 5% VAT OF [(D)+(E)+(F)]                     |  |  |  |                       |
| H | TOTAL PROJECT COST; [(D) + (E) + (F) + (G)] |  |  |  | <u>≤Php988,342.74</u> |

Note: Based from the approved program of works and drawings.