


Supply and Application of High Strength Waterproofing Membrane on concrete roof deck of PPA Head Office Bldg.

SCOPE OF WORK

- 1. Mobilization and preparation of materials, equipment, tools including consumables and manpower to the job site.**
- 2. Surface Preparation**
 - Cleaning the surface area to remove dirt & other contaminants by chemical cleaning & hand tools.
 - Removal of old waterproofing material by hand tools or electric-power equipment to ensure the maximum adhesion of waterproofing material to be applied.
- 3. System Application for Concrete Roof Deck**
 - Sealing & patching of all gaps, cracks, hairlines and holes of the concrete substrate. Curing.
 - Apply 1 coat of High Strength Concrete Penetrating Sealer on surface area. Curing.
 - Apply 1 coat of High Strength Flexible Cementitious Membrane. Curing.
 - Apply 2 coats of High Strength Weatherseal. Curing.
 - Cleaning and clearing of work area after completion of project.
- 4. Total Area:** 480 m²
- 5. Project Duration:** 15 working days
- 6. Approved Budget for the Contract:** Php 696,000.00



EDUARDO C. ALVAREZ
GSD Manager