TO : **PHILIPPINE PORTS AUTHORITY**
PORT OF DAPITAN
DAPITAN CITY

Date

We hereby offer to supply you with the item(s) listed hereunder with our price quotation shown opposite each and under the terms and conditions on the reverse side. We certify in this connection, that our establishment is the manufacturer/licensed distributor,dealer of item(s) listed below, and that at least 60% of the capital thereof is owned by Filipino citizens. Proof to this effect may submitted if required.

Item	Qty	Unit	Items & Specifications	Unit Cost
			Job Order:	
1	1	lot	Supply of Labor, Tools ,Materials &	
			Equipment for the	
			Provision of Elevated Water Tank for PICO, Transient Dormitory, and PPD Building	
			Project Duration = 31CD+60CD Delivery=91 CD	
			Approved Budget for the Contract = 869,212.55	

Signature of Supplier

Name of Supplier / Contractor

Tel. No. / Cellphone No.

DETAILED COST ESTIMATES

Date

Project: **Provision of Elevated Water Tank for PICO, Transient Dormitory, and PPD Building**

Location: **Port of Dapitan, Dapitan City, Zamboanga del Norte**

Item of Work		Unit	Quantity	Unit Cost	Amount
	PROVISION OF ELEVATED WATER TANK				
1.01	Demolition and Restoration Works	sq.m.	4.00		
1.02	Excavation Works for the Elevated Water Tank Foundation	cu.m	6.00		
1.03	Rebar Works for the foundation	kg	474.00		
1.04	Concreting Works for the foundation	cu.m	3.59		
1.05	Steel Woorks for the Frame	kg	2,687.02		
1.06	Provision of 3-Units 3,200 L Polyethylene Water Tank	units	3.00		
1.07	Electrical Works	unit	1.00		
1.08	Plumbing Works for Waterline	unis	4.00		
1.09	Painting Works	unit	1.00		
		TOTAL BID PRICE			-

In Words : _____

_____

Authorized Signature / Contractor

Name of Construction Firm