

Philippine Ports Authority
PORT MANAGEMENT OFFICE – NCR SOUTH

BILL OF QUANTITIES

Maintenance of existing pavement at a portion of Boston Street, South Harbor, Port Area, Manila.

Project Name

NO. (1)	DESCRIPTION OF WORK (2)	UNIT (3)	QTY. (4)	UNIT PRICE (Pesos) (5)	AMOUNT (Pesos) (4) x (5)
BILL NO. I	General Expenses	Lot	1.00		
1.1	Mobilization/Demobilization	Lot	1.00		
1.2	Occupational Safety and Health 1.2A First Aide System / PPE/ Admin Controls	Lot	1.00		
TOTAL FOR BILL NO. I					

Philippine Ports Authority
PORT MANAGEMENT OFFICE – NCR SOUTH

BILL OF QUANTITIES

Maintenance of existing pavement at a portion of Boston Street, South Harbor, Port Area, Manila.

Project Name

NO. (1)	DESCRIPTION OF WORK (2)	UNIT (3)	QTY. (4)	UNIT PRICE (Pesos) (5)	AMOUNT (Pesos) (4) x (5)
BILL NO. II	Elevation of Concrete Pavement				
II.1.	Concrete cutting -cut an existing pavement as per approved plans and specifications	I.m.	48.10		
II.2	Concrete Breaking - Break existing pavement as indicated in the approved plans - Haul and dispose concrete debris to the nearest dump site	Cu.m.	20.09		
II.3	Concrete Fill - Concreting works in accordance with the approved plans and specifications - Installation and stripping of formworks	Cu.m.	31.00		
TOTAL FOR BILL NO. II					

Philippine Ports Authority
PORT MANAGEMENT OFFICE – NCR SOUTH

BILL OF QUANTITIES

Maintenance of existing pavement at a portion of Boston Street, South Harbor, Port Area, Manila.

Project Name

NO. (1)	DESCRIPTION OF WORK (2)	UNIT (3)	QTY. (4)	UNIT PRICE (Pesos) (5)	AMOUNT (Pesos) (4) x (5)
BILL NO. III	Provision of drainage system				
III.1.	Grade 40 reinforcements -Fabrication and installation of rebars in accordance with the approved plans and specifications	kgs	403.00		
III.2	100mm CHB - Laying of CHB in accordance with the approved plans & specifications - Plastering of wall, 16mm thk (1 side)	Sq.m.	16.80		
III.3	Metal Works - Fabrication and installation of rebars in accordance with the approved plans & specifications	lot	1.00		
III.4	Painting works -Supply, deliver, surface preparation & painting/repainting metal surfaces	Sq.m.	16.48		
TOTAL FOR BILL NO. III					