

TERMS OF REFERENCE

MAINTENANCE OF PMO NCR-NORTH PORT POLICE OFFICE BUILDING NORTH HARBOR, TONDO, MANILA (MPF-NCN-02-2025)

I. RATIONALE

Philippine Ports Authority-Port Management Office-NCR North aims to ensure that its port facilities are properly maintained to properly cater and provide efficient services that will meet the demands of its port users.

A well-maintained administrative building not only enhances the productivity of PMO employees but also reflects the Authority's standards and values to port users and visitors.

II. OBJECTIVE

PPA PMO-NCR North intends to perform preventive maintenance to the port facilities to preserve the facility asset. The project shall only removal and replacement of roof and ceiling of the Port Police Office Building.

The procurement of the project shall be made through Alternative Mode of Procurement particularly Small Value Procurement in accordance with Section 34, of the implementing rules and regulations of the Republic Act No. 12009 or New Government Procurement Act.

III. SCOPE OF WORKS AND SERVICES

BILL NO. 1 GENERAL EXPENSES

1.1 Mobilization / Demobilization

1.2 Provide construction safety and health program in the execution of project

BILL NO. 2 ROOF AND CEILING REPLACEMENT

2.1 Removal of existing roof, gutter, flashing and downspout

2.2 Supply, deliver and install roof, gutter, flashing and downspout

2.3 Removal of existing ceiling boards and ceiling joists

2.4 Supply, deliver and install 4.5mm thk. Fiber cement board ceiling on wooden joists

2.5 Prepare surface and paint ceiling surface with 3-coats flat latex

2.6 Prepare surface and paint ceiling surface with 3-coats flat white enamel water-based paint

IV. ELIGIBILITY OF THE SERVICE PROVIDER

The prospective contractor must submit the following equipment and documentary requirements:

A. Equipment Required :

Quantity	Description
20-set/s	H-Frame Scaffoldings, Owned or Leased
5-set/s	Platform Catwalk, Owned or Leased

B. Prospective bidders shall submit Quotation together with the herein documents:

1. PCAB License – At least Small “B” for Building
2. PhilGEPS Registration
3. BIR Certificate of Registration
4. Income/ Business Tax Return
5. Duly Notarized Omnibus Sworn Statement

V. APPROVED BUDGET CONTRACT

The Approved Budget for the Contract (ABC) shall be the amount **Eight Hundred Ninety-Four Thousand Nine Hundred Fifty Pesos (Php 894,950)**.

VI. CONTRACT DURATION

The target number of days to complete the project is thirty-seven (37) days reckoned upon receipt of by the winning bidder of the Notice to Proceed (NTP).

VII. TERMS OF PAYMENT

The payment shall be paid in full to the contractor upon completion and acceptance of the project by PPA PMO-NCR North subject to accounting and auditing rules and regulations.

VIII. PERFORMANCE SECURITY

To guarantee the faithful performance by the winning bidder of its obligations under the contract in accordance with the Bidding Documents, it shall post a performance security prior to the signing of the contract. The winning bidder shall ensure that the performance security remains effective until the issuance of the Certificate of Final Acceptance.

The performance security shall be in the form chosen by the procuring entity and in the amount not less than the required percentage of the total contract price in accordance with the following schedule:

Form of Performance Security	Amount of Performance Security (Not less than the required percentage of the Total Contract)
a) Cash or cashier's or Manager's check issued by a bank	Ten percent (10%)
b) Bank draft or guarantee or irrevocable Letter or Credit issued by a bank. If issued by a foreign bank it shall be confirmed or authenticated by a local bank.	
c) Surety Bond callable upon demand issued by a surety or insurance company dully certified by the Insurance Commission as authorized to issue such security	Thirty percent (30%)

IX. LIQUIDATED DAMAGES

In case the prospective Contractor fails to perform satisfactorily the maintenance activities within the agreed contract period, the Contractor shall be held liable for damages for the delay and shall pay the Procuring Entity liquidated damages, an amount equal to one-tenth (1/10) of one-percent (1%) of the cost of the delayed project scheduled for completion, for every day of delay until such project is finally accomplished and accepted by the procuring entity concerned.

X. RESPONSIBILITY OF THE PROSPECTIVE CONTRACTOR

- a. The Contractor shall at all times utilize the most cost effective and widely accepted standards and practices in accomplishing the maintenance activities provided for in the Terms of Reference.
- b. The Contractor shall keep the PPA fully informed and updated on all matters relating to the maintenance activities accomplished.

XI. RESPONSIBILITY OF THE PHILIPPINE PORTS AUTHORITY

- a. For and in consideration of full, satisfactory and full performance by the Contractor of all maintenance activities provided for in the Terms of Reference (TOR), PPA shall pay the full amount considered to the Lowest Calculated Responsive Bid of all the bid proposals submitted.
- b. PPA shall assign a qualified engineering personnel to monitor, supervise and oversee the work direction of the maintenance activities being implemented by the Contractor to determine the actual progress and accomplishments of the project.

X. GENERAL REQUIREMENTS AND TECHNICAL SPECIFICATIONS OF PROJECT

ITEM 01 : DEMOLITION AND REMOVAL WORKS

A. DESCRIPTION OF THE PROJECT ITEM

- The work includes the furnishing of all labor, materials and equipment required to carry out the demolition and removal of old structures, port accessories and obstructions including demolition of miscellaneous concrete curbs etc., as required for the execution of the Contract.
- The Contractor shall submit the proposed methodology or procedure of demolition work with detailed drawings and calculations if necessary, to the Engineer for approval, before the execution of the Works.
- The Contractor shall keep all pavements and landing areas to and from the site of the disposal area clean and free of mud, dirt and debris during and after the execution of disposal. Disposal of debris and materials shall be as directed by the Engineer.

B. GENERAL PROVISIONS

- The Contractor shall be deemed to have satisfied himself of the site conditions, and to have included in his unit prices provision for all risks that may arise during or in connection with the work.
- The demolition shall be carried out by approved methods and equipment such as concrete breakers, gas-cutters, hydraulic jacks, compressed air disintegrators, etc., however, no blasting shall be used unless approved in writing by the Engineer and after obtaining the written permission of the concerned authorities.
- The Contractor shall provide suitable equipment, skilled labor and appropriate temporary works such as scaffoldings to ensure safety in his demolition works as well as in the adjacent area.
- Contractor shall demolish all the structural members above the level on which the subsequent and permanent works under this Contract will begin. To this end, the temporary construction works such as excavation shall be conducted by the Contractor.
- Materials coming from the demolition works, except general earth, shall remain the property of the Procuring Entity, the designated part of which shall be stored by the Contractor at places specified by the Engineer/ Accepting authority. Receiving copy of Turn-Over Report shall be provided.
- In case of demolition of wharf deck and platform, the contractor shall ensure that no debris will be remained/deposited at seabed.

C. INTERFERENCE WITH PORT OPERATIONS

- During the execution of the work, the Contractor shall not interfere with the shipping, navigation and other traffic in the port.
- The Contractor shall make arrangements with the operations people on the schedule of demolition and related works to keep port operation activities undisturbed at all times.
- Prior to commencement of the demolition works, the Contractor shall inform/announce to port users the schedule of disconnection of utilities.

D. STORAGE AND DUMPING

- Prior to the commencement of the demolition work, the Engineer shall submit to the Contractor a list in which all the materials to be salvaged and overhauled, as property of PPA, and the description of the location of their storage. Materials embedded in concrete units shall not be salvaged.
- The Contractor shall separate materials to be salvaged from debris. Salvaged materials shall be loaded, transported and unloaded by the Contractor at the specified locations.
- The Contractor may dump debris or extracted rocks on land areas but out of the site, which areas shall be procured and prepared at his own expense. In this case, safety measures shall be undertaken in the transporting, unloading, covering and others as requested by the Engineer.
- The approximate distance of the disposal site from the project site is about five (5) kms., as designated by the PMO thru the implementing office.

E. EXECUTION OF THE PROJECT ITEM

- Prior to the commencement of demolition works, the alignment of new construction works to existing structure shall be checked.
- The width and alignment of portion of existing structure to be demolished shall be marked by paint.
- With these lines as guides, concrete shall be broken and reinforcing bars cut, such that panels or portions of the structure can be lifted out for disposal elsewhere outside of the operational work area.
- Rocks removed from existing slope protection shall be stored for re-use in new construction.

- Demolish pavements, curbs, fences, utilities, services, navigation aids and the likes as determined in the field for each project and as shown on the drawings or as directed by the Engineer.
- Materials coming from the demolition works shall be properly disposed by the Contractor.

F. SAFETY

- During the course of survey and clearing, any obstacles which are recognized and seemed to be explosive or hazardous to workers shall be removed from the site by the proper Authority.
- At the end of each day's work, the Contractor shall keep the workplace in safe condition and clean so that no part is in danger of falling or creating hazard to personnel or equipment.

ITEM 02 : ROOFING AND CEILING

SCOPE OF WORK

The work shall include all labor, materials and equipment necessary to install roofing/ceiling materials, complete as shown on the drawings and as specified herein.

GENERAL REQUIREMENTS

The work includes the installation of roofing sheets, steel ridge roll, gutter, flashing and all miscellaneous roofing items not specifically noted, but required for the proper execution of the work. Surfaces shall be thoroughly dry and clean, painted with protective coatings and free from any defect that might affect the metalwork.

All miscellaneous roofing items shall be fabricated and installed in accordance with the requirements as specified herein or as indicated in the drawings. The Contractor shall verify all measurements in the field, submit shop drawings to the Engineer showing sizes, gauges, detailed of construction, method of assembly and installation. Fabrication of work shall not commence until all shop drawings are approved by the Engineer.

Roofing/Ceiling materials and accessories shall be carefully handled and stored to prevent damage to the damage to the surface and edges.

MATERIALS

Roofing shall be of MILANO type corrugated G.I. sheets or equivalent. Ridge rolls, fascia, gutters, capping, flashings, fastening devices and all similar items required to complete the roofing installations shall be colorbonded G.I. sheets. Thickness shall be as indicated in the drawings.

INSTALLATION

Installation of roofing materials including ridge rolls, roof gutters, flashing and other accessories shall be performed with precise method and a manner in accordance with the specifications, professional skilled experienced and that the roofing materials shall be installed to enable to withstand the wind and rain.

ITEM 03 : PAINTING WORKS

A. GENERAL REQUIREMENT

The work shall include all labor, materials, equipment, plant and other facilities and the satisfactory performance of all works necessary to complete all field painting and as specified herein. All paints and coatings shall be applied by painting subcontractors and workmen approved by the PPA Engineer.

B. SCOPE

The scope of painting works shall only be the all the ceiling surfaces at the Port Police Office Building.

C. RIGHT OF REJECTION

Exterior painting or interior finishing shall be done under conditions which shall not jeopardize the appearance or quality of the painting or finishing in any way. The Engineer shall have the right to reject all material or work that is unsatisfactory, and require the replacement of either or both at the expense of the Contractor.

D. PROTECTION OF THE WORK

The Contractor shall endeavor to protect the work of others during the time painting work is in progress. The Contractor shall be responsible for any and all damage to any other work in the course of his painting job.

Protective coverings shall be used to protect floors, fixtures, and equipment while painting, care shall be exercised to prevent paint being spattered onto surfaces which are not to be painted.

E. WORKMANSHIP

All painting work shall be first class and in accordance with the best standard practices of the trade.

The Contractor shall examine carefully all surfaces to be painted and before beginning any of his work shall make sure that the work of other trades has been installed in a workman like condition ready to receive paint. Metal surfaces shall be clean, dry and free from mill scale, rust, grease, oil or any other substance which could affect the quality of the painting.

Paint shall be applied at the proper consistency and each coat shall be brushed evenly free of brush marks, sags, and runs. Care shall be exercised to avoid lapping of paint on glass or hardwares. Paint shall be sharply applied to required lines.

Finished paint surfaces shall be free from defects or blemishes. Surfaces from which such paint cannot be removed satisfactorily shall be painted or repainted, as required to produce a finish satisfactory to the Engineer.

Succeeding paint coatings shall be applied only when the previous coat is hard and dry.

All painting materials shall be used in strict accordance with manufacturers directions, spread or flowed on smoothly with proper film thickness and without runs, sags, skips or other defects.

F. STORAGE OF MATERIALS

All painting materials and equipment not for immediate use shall be stored in a room approved by the Engineer for that purpose. The receiving, opening and mixing of all paint shall be removed from the premises at the end of each day's work, or stored in metal containers with metal covers.

G. PREPARATION OF PAINT

Paint containers shall be delivered to the job site in manufacturer's unopened containers and shall be opened only when required for use. Paint shall be mixed only in the designated room or space in the presence of the Engineer or his representative. Paint shall be thoroughly stirred or agitated to uniformly smooth consistency suitable for proper application. Unless otherwise specified or approved, no materials shall be reduced, changed, or used except in accordance with manufacturer's label or tag on container. In all cases, paint shall be prepared and handled in a manner to prevent deterioration and inclusion of foreign matter.

H. CLEAN-UP

Upon completion of his work, the Contractor shall remove all surplus materials. All paint spills shall be removed and the entire premises shall be cleaned of all rubbish, and debris, caused by his work. He shall present the work clean and free from blemishes so that it is acceptable in every way. All glass, fixtures and doors shall be cleaned of paint spots and polished, and the job made for occupancy by the owner.

I. MATERIALS

1. **Materials** – The Contractor may substitute other paint materials for those specified in Section 15.12 provided he first receives written approval from the Engineer stating that said proposed substituted materials are equal to that specified and are approved for use. The painting material shall be delivered to job site in original containers properly labeled without evidence of tampering, substitution of contents, or of deterioration. A complete list of materials proposed for use shall be submitted for the Engineer's approval.
2. **Colors and Samples** – All finish colors shall be as selected by the Owner. In multicoat work using color pigmented paints, each coat shall have sufficient variation of color to easily distinguish it from preceding coat.

Using specified or approved materials, 3 sample panels of each finish, including all coats thereof shall be prepared and submitted for the Owner's approval. Completion work shall match approved colors and samples.

J. PREPARATION OF SURFACES

All concrete and masonry surfaces shall be cured thirty days prior to painting. Dirt, dust, oil, grease, efflorescences, loose cement, chalk and other deleterious matter shall be removed and surface roughened when necessary to insure good paint adhesion. the method of surface preparation shall be left to the discretion of the contractor, but results obtained shall be satisfactory to the Engineer. Before application of resin emulsion paint, surfaces shall be prepared in accordance with manufacturer's directions. Before application of oil base or latex paints, surfaces shall be tested for presence of alkali; if alkali is present, neutralized as recommended by the manufacturer of the paint materials to be applied.

Woodwork – Unless already properly sanded, woodwork shall be sandpapered smooth by hand. Before priming surfaces, knots, pitch pockets and sap streaks shall be thoroughly cleaned of residue and touched up with shellac varnish coating. After priming surface, nail holes, cracks and depressions shall be neatly filled with putty or other approved filler, colored to match required finish. Enamel undercoats shall be sanded by hand (with No. 00 sandpaper) and dusted clean before applying succeeding coat.

K. APPLICATION OF PAINT

1. General Scope – All painting and finishing shall be performed by skilled craftsmen. Each coat of paint shall be applied with proper consistency, evenly, free of laps, sags and runs and cut sharply to required lines. Paint shall be applied only under dry and dust free conditions that will insure properly finished surfaces, free of defects and blemishes unless otherwise directed by the Engineer. Paint shall not be applied when temperature is likely to be above 90°F. Sufficient time shall be allowed between application of coats to insure proper drying of the preceding coat. All primer and intermediate coats shall be unscarred and completely integral at time of application of each succeeding coat. The Engineer shall be notified when each coat has been applied and is ready for inspection; until coat is inspected and approved by the Engineer, no succeeding coats shall be applied. Whenever two coats of a dark colored paint are specified the first coat shall contain sufficient powdered aluminum to act as an indicator for proper coverage when applying the second coat.
2. Method of Application – Paint should be applied by brush, spray, or other application method approved by the Engineer.
3. Priming and Back Painting
 - a. Priming – Before installation, all surfaces of millwork which are to be painted shall be primed giving particular attention to sealing of cross-grained surfaces. In all cases, all work shall be primed as soon as possible after delivery to buildings, before or after installation, as

required, or in case prefabricated items, at fabricator's shop or mill before shipment, if practicable. Except as otherwise specified, primings shall consists of first coat herein after specified under "Finishes".

- b. Back-Painting – Woodwork, millwork and casework to be installed against concrete, masonry or plaster shall be back painted with one coat of exterior oil paint.

L. PAINTING SCHEDULE

Paint manufacturers shall be BOYSEN, DAVIES or approved equal.

CEILING SURFACES

- 1. Fiber Cement Board – 3 coats flat latex
- 2. Wooden Ceiling – 3 coats enamel water-based paint

ITEM 4 : PROJECT BILLBOARD

A. SPECIFICATION

The Project Billboard shall be installed at location(s) designated by the PPA Engineer. (for reference, **Annex A** is attached herein)

The size and specifications of materials for the standard billboard shall be 4ft. x 8ft. (1,200mm x 2,400mm) using ½ inch (12mm) marine plywood or tarpaulin poster on 3/16 inch (5mm) marine plywood.

Project billboards shall not contain Name(s) and/or picture(s) of any personages.

ITEM 05 : SAFETY SIGNAGES AND BARRICADES

A. DESCRIPTION

This work includes the furnishing and installing of safety signages and barricades in accordance with the specifications and to the details shown below in the drawings, or as directed by the Engineer.

B. SPECIFICATION

The Signage's and Barricades shall be installed at location(s) designated by the PPA Engineer.

The sizes of the standard signages shall be 2-2/3ft x 4ft (800mm X 1,200mm) for fixed type and 2ft x 2-2/3ft (600mm x 800mm) for mobile type. For barricade standard 2ft x 2-2/3ft (600mm x 800mm) shall be provided.


The materials to be used for signages and barricades are ½ inch (12mm) marine plywood or tarpaulin poster on 2" x 2" (50mm x 50mm) good lumber frame (see drawing below).

The printing or painting shall be the discretion of the PPA Engineer.

XI. RESERVATION CLAUSE

The employees of the Contractor are not employees of the PPA, and thus, the latter shall not in any way be responsible for any liability resulting or arising from the conduct of activities of the former, in whatever kind or nature.

Prepared by:


Rouella Marie D. Sabate
Supervising Engineer A



Approved by:


Jenneliza D. Rebong
Port Manager
PMO-NCR North