PHILIPPINE PORTS AUTHORITY
Port Management Office-Zamboanga
R.T. Lim Boulevard, Port Area
Zamboanga City
Telephone No. (062) 991-2037

CANVASS FORM

_____

_____

_____
(Supplier)

Date: Nov. 15, 2019

PR Number: ZAM 279-19 (M)

Gentlemen: Please quote your government price/s for the article/s listed hereunder:

Item No.	Qty	Unit	Articles	Unit Cost	Amount
1	1	1	**Supply of materials, labor, and equipment for the Rehabilitation of Dilapidated Admin. Building Ground Floor Tiles and Comfort Room Ceiling, Plumbing Fixtures and Amenities, Port of Zamboanga, Zamboanga City**		
			Scope of Work: A. Removal & Disposal Works – 289.20 sq.m. 1. Removal and Disposal of Dilapidated Floor & Wall Tiles, Ceiling Panel, Electrical Fixtures, Plumbing Fixtures, Doors & Windows B. Electrical & Plumbing Works – 1 lot 1. Installation of Plumbing Fixtures/Fittings (pipes, 2-urinals, 4-water closets, 2-shower sets, 5-Lavatory sets, 8-Floor Drain, etc.) 2. Installation of Electrical Fixtures/Fittings (wires, LED lightings, boxes, exhaust fan, etc.) – 28 E-units C. Finishing & other Civil Works 1. Installation & painting of Ceiling Board – 21.37 sq.m 2. Installation of CR floor and wall tiles – 119.40 sq.m 3. Installation of Hallway ground floor tiles – 144.66 sq.m 4. Installation of toilet wooden cabinets, toilet cubicles (phenolic board) & wall-mounted mirrors for male & female toilets. 5. Installation of treated & pre-painted wooden panel door – 2 units & PVC Door – 3 units 6. Installation of UPVC Awning Windows – 2 sets & Casement Window – 1 set 7. Provision of concrete lavatory counter top - 0.18 cu.m and CHB wall – 8.32 sq.m. Minimum Equipment Requirements: Minor tools (jackhammer, scaffoldings, masonry chisel, handheld hammer, metal saw, etc.) **Terms and Conditions:** 1. Term of Payment - 100% Payment upon Completion 2. Project Duration - 45 calendar days 3. Performance Security - in accordance with schedule provided under Section 39.2 of RA 9184 4. Warranty: One (1) year after acceptance 5. Quotations should be submitted in a sealed envelope x-x-x-x-x-x-x-x-x-x-x-x-x-x-x-x-x-x-x-x-x-x-x-x		

Please submit your quotation on or before 2:00 PM November 26, 2019.

Very truly yours,

MAHSON S. UKKOH
Supervising Engineer A/ TWG Member

JOHNSON D. KHO
ESD Manager

_____
Canvasser

The above price/s and/or quotation/s for the article/s you wish to purchase/repair is/are available within _____ days from the date of quotation.

_____
AUTHORIZED SIGNATURE

_____
Name of Supplier/Firm/Company

Date quoted: _____

Price Valid for: _____

Terms: