



## SUPPLEMENTAL/BID BULLETIN NO. 1

### SUPPLY, DELIVERY AND INSTALLATION OF AIR CONDITIONING UNITS IN PPA HEAD OFFICE AND PORT MANAGEMENT OFFICES

TO : All Prospective Bidders  
: Members, HO-BAC-PGCS  
: Others Concerned

Relative to the Bidding Documents for the Supply, Delivery and Installation of Air Conditioning Units in PPA Head Office and Port Management Offices (BAC PGCS-008-2021), which was posted in the PhilGEPS and PPA Websites on 19 May 2021, please be informed of the following amendments thereto, as follows:

#### 1. SPECIAL CONDITIONS OF THE CONTRACT

GCC Clause	
2.2	<p>The terms of payment shall be as follows:</p> <ul style="list-style-type: none"> <li>• Payment of 65% of the contract price shall be made after Delivery, Inspection and Acceptance of the one hundred sixty four (164) Brand New Air Conditioning Units.</li> <li>• Payment of the remaining 35% of the contract price shall be made after Installation and Commissioning of the one hundred sixty four (164) units of Brand New Air Conditioning Units.</li> </ul>

#### 2. SCHEDULE OF REQUIREMENTS

Item Number	Description	Quantity	Total	Delivered, Weeks/Months
	Supply, Delivery and Installation of Air Conditioning Units in PPA Head Office and Port Management Offices	164 units	164 units	Within ninety (90) calendar days from receipt by the winning bidder of the Notice to Proceed

#### 3. TECHNICAL SPECIFICATIONS

" xxx xxx xxx

## TECHNICAL SPECIFICATIONS

ITEM	DETAILS		QUANTITY	
9	INVERTER CEILING MOUNTED TYPE AIR-CONDITIONING EQUIPMENT 5.0 TR (6.0 Hp)	Unit Model	Inverter	11
		Unit Type	Ceiling Mounted	
		Cooling Capacity	19,500 – 47,800	
		Power Supply (V/Ph/Hz)	220/1/60	
		Power Consumption (Kw)	1.90 – 5.77	
		Type of Control	Wireless Remote	
		Air Filter	Washable	
		Refrigerant Type	R-32	

## DELIVERY AND INSTALLATION

2. Specifically, the work shall involve the following:

b. To supply, deliver and install the following Air-conditioning units at the locations indicated:

LOCATION			DESCRIPTION	QUANTITY
HEAD OFFICE			5 TR (6.0 Hp) INVERTER Ceiling Suspended Type Air Conditioner	11
Ground Floor	TD Staff	1		
	Canteen	3		
3 <sup>rd</sup> Floor	CD Staff	1		
4 <sup>th</sup> Floor	PCMD Staff	2		
	PPDD Staff	1		
5 <sup>th</sup> Floor	IAD Staff	1		
	ICTD Staff	1		
	LSD Staff	1		

## 4. TERMS OF REFERENCE

“ xxx xxx xxx

## 4. TECHNICAL SPECIFICATIONS

ITEM	DETAILS		QUANTITY	
9	INVERTER CEILING MOUNTED TYPE AIR-CONDITIONING EQUIPMENT 5.0 TR (6.0 Hp)	Unit Model	Inverter	11
		Unit Type	Ceiling Mounted	
		Cooling Capacity	19,500 – 47,800	
		Power Supply (V/Ph/Hz)	220/1/60	
		Power Consumption (Kw)	1.90 – 5.77	



		Type of Control	Wireless Remote	
		Air Filter	Washable	
		Refrigerant Type	R-32	

## 7. DELIVERY AND INSTALLATION

7.2 Specifically, the work shall involve the following:

b. To supply, deliver and install the following Air-conditioning units at the locations indicated:

LOCATION			DESCRIPTION	QUANTITY
<b>HEAD OFFICE</b>				
Ground Floor	TD Staff	1	5 TR (6.0 Hp) INVERTER Ceiling Suspended Type Air Conditioner	11
	Canteen	3		
3 <sup>rd</sup> Floor	CD Staff	1		
4 <sup>th</sup> Floor	PCMD Staff	2		
	PPDD Staff	1		
5 <sup>th</sup> Floor	IAD Staff	1		
	ICTD Staff	1		
	LSD Staff	1		


## 9. PAYMENT

- Payment of 65% of the contract price shall be made after Delivery, Inspection and Acceptance of the one hundred sixty four (164) Brand New Air Conditioning Units.
- Payment of the remaining 35% of the contract price shall be made after Installation and Commissioning of the one hundred sixty four (164) units of Brand New Air Conditioning Units.

Issued this 4<sup>th</sup> day of June 2021.

THE BIDS AND AWARDS COMMITTEE:

By:

  
**MARK JON S. PALOMAR**  
 Chairperson, HO-BAC-PGCS