

BIDS AND AWARDS COMMITTEE OF PMO BICOL  
SUPPLEMENTAL BID BULLETIN NO. 1-2021



To : All prospective Bidders  
Members, BAC  
Other Concerned

Subject : Modification of Entries on the Bill of Quantities posted in the Philgeps dated January 20, 2021

Project: Repair of Breakwater No. 1/Berth No.1, Port of Legazpi City  
(Contract No. BCL 21-01)

In reference to the published Invitation To Bid dated January 20, 2021, this Supplemental Bid Bulletin is issued to modify the inadvertently interchanged data inputs on the Bill of Quantities

**FROM**

**BILL OF QUANTITIES**  
REPAIR OF BREAKWATER NO.1/ BERTH NO.1  
PORT OF LEGAZPI CITY  
CONTRACT NO. BCL 21-01

ITEM NO.	DESCRIPTION OF WORK (2)	UNIT (3)	QTY. (4)	UNIT PRICE (Pesos) (5)	AMOUNT (Pesos) (4) x (5)
<b>1</b>	<b>GENERAL EXPENSES</b>				
1.1	Mobilization/Demobilization and Cleaning	1	L.S		
<b>2</b>	<b>DAMAGED STRUCTURES</b>				
2.1	Demolition and Disposal of Damaged Deflector Wall	77.37	In.m		
2.2	Demolition and Disposal of Damaged Curtain Wall, RC Curb and Removal of Four Bollards	79.00	In.m		
<b>3</b>	<b>DEFLECTOR WALL</b>				
3.1	Supply and Deliver to Site Type II Steel Sheet Piles	117,216.00	kg.		
3.2	Handle, Pitch and Drive Type II Steel Sheet Piles	2,442.00	In.m		
3.3	Supply and Place 50 - 100 kg. Core Rocks	254.93	kg.		
3.4	Supply and Install Steel Reinforcements	9,761.73	kg.		
3.5	Supply and Place 3,500psi Concrete for Deflector Wall	192.65	cu.m		
<b>4</b>	<b>CURTAIN WALLS, RC CURB AND MOORING BLOCK</b>				
4.1	Supply and Install Steel Reinforcements	2,784.40	kg.		
4.2	Supply and Place 3,500psi Concrete	20.38	cu.m		
<b>5</b>	<b>PCCP</b>				
5.1	Supply, Spread and Compact Aggregate Base Course	409.80	cu.m		
5.2	Construct PCCP (300mm thk.)	1,366.00	sq.m		
<b>6</b>	<b>MOORING BOLLARD</b>				
6.1	Supply and Deliver to Site 50T Mooring Bollard	4.00	set		
6.2	Install 50T Mooring Bollard	4.00	set		
<b>7</b>	<b>RUBBER DOCK FENDERS</b>				
7.1	Removal of Damaged RDF Accessories	18.00	pc.		
7.2	Supply and deliver to Site V - Type 500H x 2000L RDF	3.00	set		
7.3	Install V- Type 500H x 2000L RDF	3.00	set		
				<b>Grand Total</b>	

Submitted by: \_\_\_\_\_  
Name of Bidder  
Signature over Printed Name

**TO**

**BILL OF QUANTITIES**  
REPAIR OF BREAKWATER NO.1/ BERTH NO.1  
PORT OF LEGAZPI CITY  
CONTRACT NO. BCL 21-01

ITEM NO.	DESCRIPTION OF WORK (2)	UNIT (3)	QTY. (4)	UNIT PRICE (Pesos) (5)	AMOUNT (Pesos) (4) x (5)
<b>1</b>	<b>GENERAL EXPENSES</b>				
1.1	Mobilization/Demobilization and Cleaning	L.S	1		
<b>2</b>	<b>DAMAGED STRUCTURES</b>				
2.1	Demolition and Disposal of Damaged Deflector Wall	In.m	77.37		
2.2	Demolition and Disposal of Damaged Curtain Wall, RC Curb and Removal of Four Bollards	In.m	79.00		
<b>3</b>	<b>DEFLECTOR WALL</b>				
3.1	Supply and Deliver to Site Type II Steel Sheet Piles	kg.	117,216.00		
3.2	Handle, Pitch and Drive Type II Steel Sheet Piles	In.m	2,442.00		
3.3	Supply and Place 50 - 100 kg. Core Rocks	cu.m	254.93		
3.4	Supply and Install Steel Reinforcements	kg.	9,761.73		
3.5	Supply and Place 3,500psi Concrete for Deflector Wall	cu.m	192.65		
<b>4</b>	<b>CURTAIN WALLS, RC CURB AND MOORING BLOCK</b>				
4.1	Supply and Install Steel Reinforcements	kg.	2,784.40		
4.2	Supply and Place 3,500psi Concrete	cu.m	20.38		
<b>5</b>	<b>PCCP</b>				
5.1	Supply, Spread and Compact Aggregate Base Course	cu.m	409.80		
5.2	Construct PCCP (300mm thk.)	sq.m	1,366.00		
<b>6</b>	<b>MOORING BOLLARD</b>				
6.1	Supply and Deliver to Site 50T Mooring Bollard	set	4.00		
6.2	Install 50T Mooring Bollard	set	4.00		
<b>7</b>	<b>RUBBER DOCK FENDERS</b>				
7.1	Removal of Damaged RDF Accessories	pc.	18.00		
7.2	Supply and deliver to Site V - Type 500H x 2000L RDF	set	3.00		
7.3	Install V- Type 500H x 2000L RDF	set	3.00		
				<b>Grand Total</b>	

Submitted by: \_\_\_\_\_  
Name of Bidder  
Signature over Printed Name

All other details remain the same.

For the guidance and information of all concerned.

Issued this 2nd day of February 2021.

DENNIS M. POPATCO  
BAC Chairperson